

**SURVEY & REMONUMENTATION**

APR 29 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
	ALMONT TOWNSHIP	
1. Public Land Survey	T <u>6N</u> R <u>12E</u>	<u>A-8</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

RECEIVED FOR RECORD

95 NOV 22 PM 3:58

LIBER NO. 005 PAGE NO. 302

*Richard L. Vaughn*  
REGISTERED DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, SHELBY W. MONEY, in a field survey on May 19, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |     |        |                   |                               |            |                 |
|-----|--------|-------------------|-------------------------------|------------|-----------------|
| 1)  | GLO    | Nothing Set       |                               |            |                 |
| 2)  | LCRC   | 1975 L. 3, P. 47  | Harold Elrich                 | P.S. 18986 | Set 1/2" Iron   |
| 3)  | Survey | 1975 L. 3, P. 225 | Harold Elrich                 | P.S. 18986 | Set 1/2" Iron   |
| 4)  | Survey | 1975 L. 3, P. 227 | Harold Elrich                 | P.S. 18986 | Set 1/2" Iron   |
| 5)  | Survey | 1975 L. 3, P. 440 | Earl E. Gravlin               | P.S. 23510 | Unknown         |
| 6)  |        | 1986              | Lapeer County Road Commission |            | Found 1/2" Iron |
| 7)  | Survey | 1986 L. 7, P. 255 | Harold Elrich                 | P.S. 18986 | Found 1/2" Iron |
| 8)  | Survey | 1989 L. 8, P. 342 | Harold Elrich                 | P.S. 18986 | Found 1/2" Iron |
| 9)  | Survey | 1992 L. 10, P. 87 | Harold Elrich                 | P.S. 18986 | Found 1/2" Iron |
| 10) | Survey | 1993 L. 10, P. 31 | Harold Elrich                 | P.S. 18986 | Found 1/2" Iron |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rebar on the centerline of Bishop Road No occupation to the East  
 Found Witnesses: From Items 1 thru 5 N 70° E 66.11' 20" Apple  
 S 80° E 73.15' N.W. Corner of House  
 S 30° E 55.21' 24" Maple  
 N 80° W 24.90' 14" Maple  
 From Item 6 thru 10 N 70° E 66.11' 20" Apple  
 S 30° E 55.21' 24" Maple  
 N 80° W 24.90' 14" Maple

Distances: A-8 to M-8 (T. 6 N., R. 11 E.) North 91.12' A-8 to A-7 North 2475.3'  
 A-8 to M-9 (T. 6 N., R. 11 E.) South 2471.2'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Lapeer County Remonumentation Brass Cap stamped A-9; 30092 on found 1/2" rebar

- |      |        |  |
|------|--------|--|
| 30°  | 51.48' | Found PK, set PK/ Lapeer tag in Northwest face 12" Maple |
| 155° | 55.00' | Set PK/ Lapeer tag in Southwest face of 22" Apple        |
| 215° | 43.27' | Set PK/ Lapeer tag in Southeast face 15" Maple           |
| 270° | 25.23' | Set PK/ Lapeer tag in South face 18" Maple               |

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 7-13-95



Signed by *Shelby W. Money* Date *Nov 3, 1995*  
 Surveyor's Michigan License No. 30092