

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located in:	Corner Code #
	ALMONT TOWNSHIP	
1. Public Land Survey	<u>T. 6N. R. 12E</u>	<u>A-9</u>
	T. R.	
	T. R.	
	T. R.	
2. Property Controlling in Section	S. T. R.	
	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
	S. T. R.	

RECEIVED FOR RECORD

94 DEC -9 PH 3: 22

LIDER NO. 5 PAGE NO. 148  
*Robert D. Vaughn 149*

REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, SHELBY W. MONEY, in a field survey on MAY 19, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

"PLEASE SEE BACK OF PAGE"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" BAR 14" DEEP IN GRAVEL ROAD

"PLEASE SEE BACK OF PAGE"

CORNER IS COMMON TO M-9 / T.6N., R.11E., DRYDEN TOWNSHIP BY USAGE  
A-9 TO A-8 T.6N., R.12E. MEASURED  
A-9 TO A-10 T.6N., R.11E. MEASURED

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY


*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 12-9-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

TOWNSHIP AND COUNTY LINE COMMON TO LAPEER COUNTY AND ST. CLAIR COUNTY

SET 1/2" X 18" REBAR AND LAPEER COUNTY REMONUMENTATION BRASS CAP STAMPED M-9 & A-9; 30092

N 45° W	45.03'	FOUND, 1/2" REBAR W/CAP
S 50° W	76.80'	SET, NAIL W/LAPEER TAG IN THE SOUTHEAST FACE OF A UTILITY POLE
N 05° E	156.76'	SET, NAIL W/LAPEER TAG IN THE SOUTH FACE OF A UTILITY POLE
N 45° E	83.60'	SET, NAIL W/LAPEER TAG IN THE SOUTHEAST FACE OF A 10" ELM
S 60° E	120.38'	FOUND, OLD PK IN THE NORTH FACE OF A UTILITY POLE
S 20° E	308.24'	FOUND, THE NORTHEAST CORNER OF A HOUSE
N 35° W	45.00'	FOUND, 1/2" IRON W/CAP #33963



Signed by *Shelby W. Money* Date December 2, 1994  
Surveyor's Michigan License No. 30092

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **LAPEER COUNTY**  
 LOCATED IN: **ALMONT TOWNSHIP**  
 CORNER CODE: **A-9 / PAGE TWO OF TWO**

LIBER 0005 PAGE 0149

Register of Deeds Stamp & File Number

**A. Description of original monument and accessories and/or subsequent restoration:**

A-9}	G.L.O.	(1816)	PAGE 552	JOSEPH WAMPLER	NO WITNESSES FOUND
M-9}	G.L.O.	(1816)	PAGE 552	JOSEPH WAMPLER	NO WITNESSES FOUND
A-9}	LCRC	(1972) LIBER 0001	PAGE 553	BERNARD HENDERSON, P.S. #16043	FOUND PIPE
M-9}	LCRC	(1972) LIBER 0001	PAGE 553	BERNARD HENDERSON, P.S. #16043	FOUND PIPE
M-9}	LCRC	(1972) LIBER 0001	PAGE 415	LELAND D. BATES, P.S. #16699	FOUND IRON ROD
M-9}	WITNESS	(1972) UNRECORDED		LAPEER COUNTY ROAD COMMISSION	FOUND UNKNOWN
A-9}	LCRC	(1972) LIBER 0001	PAGE 709	BERNARD HENDERSON, P.S. #16043	FOUND UNKNOWN
M-9}	SURVEY	(1972) LIBER 0001	PAGE 711	HAROLD N. ELRICH, P.S. #18986	FOUND UNKNOWN
A-9}	SURVEY	(1975) LIBER 0003	PAGE 225	HAROLD N. ELRICH, P.S. #18986	FOUND IRON
A-9}	SURVEY	(1975) LIBER 0003	PAGE 227	HAROLD N. ELRICH, P.S. #18986	FOUND IRON
A-9}	SURVEY	(1979) LIBER 0005	PAGE 305	HAROLD N. ELRICH, P.S. #18986	FOUND IRON
A-9}	WITNESS	(1986) UNRECORDED		LAPEER COUNTY ROAD COMMISSION	FOUND IRON
A-9}	SURVEY	(1989) LIBER 0007	PAGE 255	HAROLD N. ELRICH, P.S. #18986	FOUND IRON ROD
A-9}	SURVEY	(1989) LIBER 0008	PAGE 342	HAROLD N. ELRICH, P.S. #18986	FOUND UNKNOWN
A-9}	SURVEY	(1993) LIBER 0010	PAGE 031	HAROLD N. ELRICH, P.S. #18986	FOUND IRON ROD
A-9}	SURVEY	(1993) LIBER 0010	PAGE 087	HAROLD N. ELRICH, P.S. #18986	FOUND IRON ROD

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND, 5/8" BAR 14" DEEP IN A GRAVEL ROAD

M-9}	LCRC	(1972)	LIBER 0001	PAGE 415	FOUND, S 45° W	POWER POLE	76.20'
A-9}	LCRC	(1972)	LIBER 0001	PAGE 553	FOUND, S 45° W	POWER POLE	77.00'
M-9}					FOUND, S 45° W	POWER POLE	76.20'
A-9}	LCRC	(1972)	LIBER 0001	PAGE 709	FOUND, S 45° W	POWER POLE	77.00'
M-9}	LAPEER COUNTY ROAD COMMISSION	(1972)			FOUND, S 45° W	POWER POLE	76.20'
M-9}	SURVEY	(1972)	LIBER 0001	PAGE 711	FOUND, S 45° W	POWER POLE	76.20'
A-9}	SURVEY	(1975)	LIBER 0003	PAGE 225	FOUND, S 45° W	POWER POLE	76.75'
A-9}	SURVEY	(1975)	LIBER 0003	PAGE 227	FOUND, S 45° W	POWER POLE	76.75'
A-9}	SURVEY	(1979)	LIBER 0005	PAGE 305	FOUND, S 45° W	POWER POLE	76.75'
A-9}	LAPEER COUNTY ROAD COMMISSION	(1986)			FOUND, S 45° W	POWER POLE	76.75'
A-9}	SURVEY	(1989)	LIBER 0007	PAGE 255	FOUND, S 45° W	POWER POLE	76.75'

**CORNER IS COMMON TO M-9 OF DRYDEN TOWNSHIP BY USAGE**

A-9/M-9 TO A-8 T.7N., R.12E  
 A-9/M-9 TO A-10 T.7N., R.12E

MISC D 9.00  
 REMLC 0075  
 REMONT 2.00