

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 27 PM 1:04

For corners in

| | | |
|------------------------------------|--------------------------|---------------|
| <u>Lapeer</u> (County) | Located In: | Corner Code # |
| | Almont Township | |
| 1. Public Land Survey | T <u>6N</u> R <u>12E</u> | <u>A-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Helen D. Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William E. Soderberg, in a field survey on May 7, 19 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- No GLO information for this corner
- 9-15-94 Survey recorded by Harold Elrich 18986 in liber 10, page 901 Found 1/2" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar in centerline of Bishop Road (gravel). No occupation line to the East.

Witnesses: from item 2 above

- N 70° E 26.10' Found nail 26" Oak
- S 75° W 17.58' Found nail 13" Oak
- S 25° E 53.97' Found nail in North face twin 12" W. Cherry
- North 55.88' Found to M-12 Dryden Township T6N, R 11E
- East 33.00' Found capped Iron #18986


Distances: North to M-12 Dryden Township 55.88 feet Elrich L 10, P 901; 55.88 feet measured
South to A-13 Almont Township 2596.62 feet Elrich L 10, P 901; 2596.80 feet measured
North to A-11 Almont Township 2540.75 feet Elrich L 10, P 901; 2540.70 feet measured

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard Lapeer County Remonumentation cap stamped " A 12 17635" on found 1/2" rebar.

- Az 70° 26.11' Found nail with Lapeer County tag in South face 18" Oak.
- Az 255° 17.59' Found nail with Lapeer County tag in NW face 12" Oak
- Az 160° 54.00' Found nail with Lapeer County tag in West face twin 15" Cherry
- Az 270° 18.21' Found nail with Lapeer County tag in North face 12" Cherry.

Signed by William E. Soderberg Date 12-19-96
Surveyor's Michigan License No. 17635



PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS, REGISTERED PROFESSIONAL SURVEYOR
DATE 7-16-96

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983