

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lapeer Located In: Almont Township Corner Code #
(County)

1. Public Land Survey T 6N R 12E G-2
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

RECEIVED FOR RECORD

94 DEC 29 AM 10:13

LIBER NO. 05 PAGE 188

REGISTERED DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Shelby W. Money, in a field survey on 11-14, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- Joseph Wampler, D.S. in 1817 pages 556 - 560 set post. No witnesses left.
- Gilbert Bates 1865 Pages 82 - 83 Stake.
- Survey recorded by Herbert Kobs, P.S. 14097 on 12-9-74 in liber 3, page 164, of surveys as a found 5/8" iron.
- Survey recorded by Herbert Kobs, P.S. 14097 on 11-6-80 in liber 6, page 54, of corners as found 5/8" iron.
- Survey recorded by James Bailey, P.S. 33968 on 5-13-91 in liber 9, page 367, of surveys as a found iron with cap #24588.
- Survey recorded by James Bailey, P.S. 33968 on 2-6-92 in liber 9, page 681, of surveys as a found iron with cap # 24588.
- Survey recorded by Earl Gravlin P.S. 23510 on 4-24-92 in liber 9, page 711, of surveys as a found 1/2" iron with cap # 24588.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar with cap # 24588 in woods with no fence line occupation in any direction.

Witnesses: from items 4, 5, 6, and 7 above
N 80° W 23.16' Nail in 16" Maple
S 45° W 34.66' Nail in 14" Cherry
S 40° E 10.29' Nail in 10" Maple
S 85° E 17.96' Nail in 8" Maple.

Distances: East to H-2 2891.09 (Bates 2996.40)
South to G-3 2657.58' (Bates 2653.20)
North to G-1 2946.43' (Bates 2996.40)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Placed standard Lapeer County Remonumentation cap stamped "G - 2 30092" on found 1/2" rebar.

Az 100° 17.96' Found nail, set nail with Lapeer County tag in South face 10" Maple.
Az 155° 10.30' Found nail, set nail with Lapeer County tag in West face 12" Maple.
Az 230° 34.63' Found Nail, set nail with Lapeer County tag in Southeast face 14" Cherry
Az 280° 23.14' Found nail, set nail with Lapeer County tag in North face 24" Maple

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-28-94

Signed by Shelby W. Money
Surveyor's Michigan License No. 30092



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1978
REVISED JAN. 1983

LIBER 0005 PAGE 0188