

# SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lapeer	Located In:	Corner Code #
(County)	Almont Township	
1. Public Land Survey	T <u>6N</u> R <u>12E</u>	<u>K-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD  
95 NOV 22 PM 4:03  
LIBER NO. 005 PAGE NO. 307  
*Melissa ...*  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Shelby W. Money, in a field survey on May 19, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1) GLO 1817 Page 539 Joseph Wampler Set Post.
- 2) LCRC 1977 L. 3, P. 276 Herbert J. Kobs P.S. 14097 Found 5/8" Iron Bar in pavement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rebar 3' East of centerline of pavement.  
No occupation to East, North bank of drain to West.

Found Witnesses: Item 2 ENE 32.32' Pk nail in Power Pole

Distances: North to K-1 3088.9' measured GLO 46.62 chs or 3076.92' record  
South to K-3 2548.7' measured GLO 40.00 chs or 2640.0' Record

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY  
*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 7-12-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a standard Lapeer County Remonumentation cap stamped "K-2 30092" on a new 1/2" rebar in a new monument box set by Lapeer County Road Commission replacing the found 5/8" bar.

- 90° 32.30' Found nail, found PK/ribbon, set PK/Lapeer tag in south face utility pole
- 110° 73.72' Found nail, set PK/Lapeer tag in south face 18" Oak
- 120° 65.15' Found nail, set PK/Lapeer tag in north face 10" Maple
- 165° 156.90' Set PK/Lapeer tag in east face 32" Maple



Signed by Shelby W. Money Date Nov 3, 1995  
Surveyor's Michigan License No. 30092