

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
	ALMONT TOWNSHIP	
1. Public Land Survey	T <u>6N</u> R <u>12E</u>	<u>M-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED FOR RECORD

94 DEC -9 PM 3: 21

LIBER NO. 5 PAGE NO. 147

REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on MAY 19, 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1816/1817) PAGE 528 JOSEPH WAMPLER SET POST
NO WITNESSES FOUND

"NO OTHER INFORMATION FOUND"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND, 5/8" REBAR IN THE ROCKS OF AN ANCHOR POST HOLE
FENCE LINE TO THE NORTH, SOUTH AND WEST

M-6 TO M-7 T.7N., T.12E. MEASURED 2684.92'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

TOWNSHIP AND COUNTY LINE SEPARATING LAPEER COUNTY AND ST. CLAIR COUNTY

REPLACED FOUND 5/8" REBAR IN THE ROCKS OF AN ANCHOR POST HOLE WITH
BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED #30092 / M-6 ON A 1/2" X 18" REBAR

AZIMUTH	00°	6.00'	SET,	1/2" REBAR W/TRVERSE	CAP AT EXISTING FENCE POST
AZIMUTH	90°	5.00'	SET,	1/2" REBAR W/TRVERSE	CAP AT EXISTING FENCE POST
AZIMUTH	180°	15.00'	SET,	1/2" REBAR W/TRVERSE	CAP AT EXISTING FENCE POST
AZIMUTH	255°	16.63'	SET,	NAIL W/LAPEER COUNTY TAG	IN THE NORTH FACE OF A 6" ELM
AZIMUTH	180°	205.97'	FOUND,	1/2" REBAR W/CAP #17635	~ A-6 OF BERLIN TOWNSHIP, ST. CLAIR COUNTY

APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Signed by Shelby W. Money Date DECEMBER 9, 1994
Surveyor's Michigan License No. 30092 RAY DAVIS P.S. CO. SURVEYOR
DATE 12-9-94