

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
LAPEER
(County)

Located in: ALMONT TOWNSHIP Corner Code # M-7

1. Public Land Survey
T. 6N. R. 12E.
T. R.
T. R.
T. R.

2. Property Controlling in Section
S. T. R.
S. T. R.
S. T. R.

3. Miscellaneous Property in Sec.
S. T. R.

4. Lot No. , Recorded Plat

5. Private Claims

RECEIVED FOR RECORD
94 DEC -9 PM 3:09
LIBER NO. 65 PAGE NO. 135
Melissa DeLoach
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN
Register of Deeds Stamp & File Number

I, SHELBY W. MONEY, in a field survey on SEPTEMBER 2, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. 1816/1817 PAGE 528 JOSEPH WAMPLER

SET POST NO WITNESSES FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND, 5/8" REBAR IN THE GRASS ALONGSIDE ROADWAY
FENCE LINE NORTH
GRAVEL ROAD WEST AND SOUTH
CENTERLINE ROAD SOUTH



M-7 TO M-6 T.7N., R.12E. MEASURE 2684.92'
M-7 TO M-8 T.7N., R.12E. MEASURE 2686.18'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
TOWNSHIP AND COUNTY LINE COMMON TO LAPEER COUNTY AND ST. CLAIR COUNTY

SET 1/2" X 18" REBAR AND BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED M-7; 30092

AZIMUTH 10°	35.83'	SET, NAIL WITH LAPEER COUNTY TAG IN THE NORTHWEST FACE OF A TWIN 8" APPLE
AZIMUTH 130°	15.87'	FOUND PK IN THE SOUTHWEST FACE OF A 16" ELDER, SET LAPEER TAG
AZIMUTH 200°	66.02'	SET, NAIL WITH LAPEER COUNTY TAG IN THE NORTH FACE OF A 12" MAPLE
AZIMUTH 245°	63.20'	FOUND PK IN THE NORTHWEST FACE OF A 10" ASH, SET LAPEER TAG
AZIMUTH 180°	211.20'	FOUND 1/2" REBAR (PLACED CAP #17635) A-7 BERLIN TOWNSHIP; T.6N., R.13E.; ST. CLAIR CTY

Signed by *Shelby W. Money*
Surveyor's Michigan License No. 30092

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990 Date December 2, 1994
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-9-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983

REC 0005 PLSE 135