

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

LAPEER  
(County)

Located in: ALMONT TOWNSHIP Corner Code #

1. Public Land Survey

T 6N R 12E M-9

2. Property Controlling in Section

S T R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S T R \_\_\_\_\_

S T R \_\_\_\_\_

S T R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat

5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD

94 DEC -9 PH 3: 23

LIBER NO. 5 PAGE NO. 150

*Notation on Page 151*

REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, SHELBY W. MONEY, in a field survey on MAY 19, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
"PLEASE SEE BACK OF PAGE"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND, 1/2" REBAR AND PULLED 10" LONG IRON / CHECKED AREA AND FOUND NOTHING  
SET, 18" x 1/2" REBAR WITH CAP #30092, A TEMPORARY POINT  
GRAVEL ROAD

"PLEASE SEE BACK OF PAGE"

M-9 TO M-8 T.7N., R.12E. MEASURED 2699.72'  
M-9 TO M-10 T.7N., R.12E. MEASURED 2687.00'


PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY  
RAY DAVIS & CO. SURVEYOR  
DATE 12-9-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

TOWNSHIP AND COUNTY LINE COMMON TO LAPEER COUNTY AND ST. CLAIR COUNTY  
SET 1/2" X 18" REBAR AND BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED M-9; 30092

AZIMUTH 35°	52.92'	SET,	NAIL W/LAPEER TAG IN THE SOUTHEAST FACE OF A UTILITY POLE
AZIMUTH 60°	159.55'	FOUND,	NORTHWEST CORNER BRICK OF HOUSE AT ADDRESS #1010 MACKIE ROAD
AZIMUTH 70°	31.96'	FOUND,	NAIL W/LAPEER TAG IN THE SOUTH FACE OF A UTILITY POLE
AZIMUTH 100°	28.96'	FOUND,	NAIL W/LAPEER TAG IN THE SOUTHEAST FACE OF A 10" ELM
AZIMUTH 105°	122.19'	FOUND,	OLD PK IN THE NORTH FACE OF A UTILITY POLE
AZIMUTH 175°	151.77'	SET,	NAIL W/LAPEER TAG IN THE SOUTHWEST FACE OF A UTILITY POLE
AZIMUTH 350°	45.00'	FOUND,	1/2" IRON W/CAP #33963
AZIMUTH 180°	118.84'	FOUND,	OLD PK IN THE NORTH FACE OF A UTILITY POLE

Signed by [Signature] Date December 2, 1994  
Surveyor's Michigan License No. 30092



**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **LAPEER COUNTY**  
 LOCATED IN: **ALMONT TOWNSHIP**  
 CORNER CODE: **M-9 / PAGE TWO OF TWO**

LIBER 0005 PAGE 0151

Register of Deeds Stamp & File Number

**A. Description of original monument and accessories and/or subsequent restoration:**

M-9	G.L.O. (1816)		PAGE 527	JOSEPH WAMPLER	SET POST	NO WITNESSES FOUND
	SURVEY (1973)	LIBER 002	PAGE 350	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR	
	LCRC (1973)	LIBER 002	PAGE 357	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR	
	SURVEY (1974)	LIBER 003	PAGE 045	ROBERT G. KAY, P.S. #14096	FOUND 1/2" IRON BAR	
	(1974)	UNRECORDED		LAPEER CTY ROAD COMMISSION	FOUND 1/2" IRON BAR	
	SURVEY (1975)	LIBER 003	PAGE 233	ROBERT G. KAY, P.S. #14096	FOUND 1/2" IRON BAR	
	SURVEY (1978)	LIBER 004	PAGE 577	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR	
	SURVEY (1979)	LIBER 005	PAGE 380	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR	
	SURVEY (1981)	LIBER 006	PAGE 187	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR	
	SURVEY (1981)	LIBER 006	PAGE 189	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR	
	SURVEY (1984)	LIBER 006	PAGE 787	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR	
	SURVEY (1988)	LIBER 007	PAGE 792	HAROLD N. ELRICH, P.S. #18986	FOUND 1/2" IRON	
	SURVEY (1991)	LIBER 009	PAGE 326	EARL E. GRAVLIN, P.S. #23510	FOUND 1/2" IRON	NO WITNESSES
	SURVEY (1991)	LIBER 009	PAGE 395	EARL E. GRAVLIN, P.S. #23510	FOUND IRON	
	SURVEY (1991)	LIBER 009	PAGE 520	HERBERT J. KOBS, P.S. #14097	FOUND 1/2" IRON BAR	
	SURVEY (1991)	LIBER 009	PAGE 540	EARL E. GRAVLIN, P.S. #23510	FOUND 1/2" IRON BAR	
	SURVEY (1991)	LIBER 009	PAGE 545	EARL E. GRAVLIN, P.S. #23510	FOUND 1/2" IRON	
	SURVEY (1993)	LIBER 010	PAGE 184	DONALD H. KING, P.S. #30085	FOUND 1/2" IRON BAR	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND, 1/2" REBAR AND PULLED 10" LONG IRON / CHECKED AREA AND FOUND NOTHING  
 SET, 18" x 1/2" REBAR WITH CAP #30092, A TEMPORARY POINT

SURVEY (1973)	LIBER 002	PAGE 350	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
LCRC (1973)	LIBER 002	PAGE 367	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
SURVEY (1974)	LIBER 003	PAGE 045	52.71'	N 25° E	PK'NAIL IN POWER POLE
(1974)	UNRECORDED		52.71'	N 25° E	PK'NAIL IN POWER POLE
SURVEY (1975)	LIBER 003	PAGE 233	52.71'	N 25° E	PK'NAIL IN POWER POLE
SURVEY (1978)	LIBER 004	PAGE 577	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
SURVEY (1979)	LIBER 005	PAGE 380	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
SURVEY (1981)	LIBER 006	PAGE 187	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
SURVEY (1981)	LIBER 006	PAGE 189	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
SURVEY (1984)	LIBER 006	PAGE 787	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
SURVEY (1988)	LIBER 007	PAGE 792	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
			151.82'	SOUTH	PK'NAIL IN POWER POLE
			122.14'	S 80° E	SOUTHWEST CORNER OF LARGE ROCK
SURVEY (1991)	LIBER 009	PAGE 326	53.10'	N 25° E	POWER POLE
			28.90'	EAST	END OF 12" CULVERT
			31.90'	N 50° E	END OF 12" CULVERT
SURVEY (1991)	LIBER 009	PAGE 395	52.72'	NORTHEAST	PK'NAIL IN POWER POLE
SURVEY (1991)	LIBER 009	PAGE 520	52.71'	N/NORTHWEST	PK'NAIL IN THE TOP OF AN 18" CMP
			31.97'	E/NORTHEAST	CHISELED NOTCH TOP NORTH END 15" CMP
			28.92'	E/SOUTHEAST	CHISELED NOTCH TOP SOUTH END 15" CMP
SURVEY (1991)	LIBER 009	PAGE 540	52.70'	NORTHEAST	PK'NAIL IN POWER POLE
SURVEY (1991)	LIBER 009	PAGE 545	53.04'	NORTHEAST	PK'NAIL IN POWER POLE
			151.82'	SOUTH	PK'NAIL IN POWER POLE
			122.14'	S 80° E	SOUTHWEST CORNER OF LARGE ROCK
SURVEY (1993)	LIBER 010	PAGE 184	52.72'	NORTHEAST	PK'NAIL IN POWER POLE

M-9 TO M-8 T.7N., R.12E. MEASURED 2699.72'  
 M-9 TO M-10 T.7N., R.12E. MEASURED 2687.00'