

1993

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE 93 DEC 22 PM 2:46 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

For corners in

Almont Township

Lapeer (County)

Located In: Corner Code #

- 1. Public Land Survey T 6N R 12E M-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

LIBER 5 FILE NO. 12

Register of Deeds Stamp & File Number

I, Shelby W. Money, in a field survey on October 12, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post Glo Note Page 527
L.C.R.C. L3 P17 Elrich (1975) Found 1" Pipe
L.C.R.C. L3 P331 Kobs (1977) Found 1" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pipe in Woods
Witness found Oak North Both LCRC's
found Oak South Both LCRC's

Recorded Surveys L3 P155 Elrich (1975)
Witness on 132 Forms L4 P78 Kobs (1977)
Match LCRC L4 P79 Kobs (1977)
L4 P976 Kobs (1979)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1" Pipe with 1/2" x 18" Rebar with Brass Lapeer County Remonumentation Cap 30092/M-12

A2 265° 16.62 Nail/LC Tag N Face 8" Ash
A2 55° 23.62 Nail/LC Tag S Face Twin 14" Maple
A2 10° 13.58 Nail/LC Tag W Face 20" Oak
A2 180° 18.58 Nail/LC Tag W Face 18" Oak

Grid table with columns A-M and rows 2-13. Contains numbers 1-36.



Signed by Shelby W. Money Date 12-21-93
Surveyor's Michigan License No. 30092