

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER
(County)

Located in:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>7</u> N R <u>9</u> E | <u>M-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECEIVED FOR RECORD

93 DEC 30 AM 10:15

LIBER NO. 5 PAGE NO. 47
Melissa Miles
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Huston K. Kennedy, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817 GLO - Wampler, D.S.; Set 1/2 mile post; 36" White Oak S59°W 25 lks, Iron N45°W 4lks
- 1991 Gravlin P.S. #23510; LCRC L.4, Pg. 374 - Fnd 1/2" iron rod
- 1991 Gravlin P.S. #23510; LCRC L.9, Pg. 573-575 - Fnd 1/2" iron rod; Same wits as 1991 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy P.S. #17623 - Fnd 1/2" iron rod in center of Baldwin Road which is gravel. Found 2 previous witnesses that were still existing. They were used to recover the found 1/2" iron rod.

I accepted the found 1/2" iron rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12 1/2" x 24" iron rod with 3" diameter brass cap
- N25°42'E 69.33' Set nail w/remon. tag West face 8" Hickory
- S51°26'E 49.78' Set nail w/remon. tag North face 6" Basswood
- S43°25'E 60.36' Set nail w/remon. tag North face 10" Elm
- S49°35'W 41.17' Set nail w/remon. tag East face 10" Elm
- N79°20'W 31.16' Set nail w/remon. tag South face 6" Elm



Signed by Huston K. Kennedy

Date 11/24/93

Surveyor's Michigan License No. 17623