

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

LAPEER (County)

Located In: LAPEER TWP.

Corner Code #

RECEIVED FOR RECORD

99 JAN -6 PM 1:45

Melissa DaVaugh REGISTER OF DEEDS LAPEER MICHIGAN

451

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 7 R 10 A-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, MICHAEL G. HAY, in a field survey on MARCH 3 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

GLO NO CORNER SET BY ORIGINAL SURVEY
NO DATE-GILBERT BATES STONE 30-16-12 EARTHEN E BRICK W OAK 22 N67W 19 B OAK 19 N30 1/2 W 157
1977-EARL E. GRAVLIN P.S. 23510 L3 P403 FOUND 5/8" IRON EAST 33.45' 20" STUMP N45W 40.23' WOOD GATE POST N30W 61.58' NAIL IN 4" ELM
1977-EARL E. GRAVLIN P.S. 23510 L4 P375 FOUND 5/8 ROD (SAME WITNESS AS ABOVE)

Signature and date 9-17-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998-MICHAEL G. HAY P.S. 41101 FOUND P.K. NAIL 1.0' WEST OF CENTER LINE OF BALDWIN AND TREE LINE AND FENCE RUNNING TO THE WEST.

A-8 TO A-7 2645.08' (M)
A-8 TO A-9 2652.84' (M) 2652.84' (R-GRAVLIN)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD REMON CAP ON 1/2" IRON IN PLACE OF P.K. NAIL IN MONUMENT BOX.
N80E 33.41' NAIL IN FENCE POST
EAST 32.97' NAIL AND TAG LAPEER WITNESS IN FENCE POST
S50W 48.12' NAIL AND TAG LAPEER WITNESS IN UTILITY POLE
NORTH 131.89' MON BOX WITH REMON CAP



Signed by Michael G. Hay Date 12-30-98
Surveyor's Michigan License No. 41101

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993