

MAR 29 1999

SECTION

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER  
(County)

Located In:  
LAPEER TWP.

Corner Code #

A-9

- 1. Public Land Survey T 7 R 10
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, MICHAEL G. HAY, in a field survey on MARCH 3, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1822-JOSEPH WAMPLER D.S. SET POST AT INTERS W BOUNDARY 172' S OF POST W OAK 10 N14E 79 ASPEN 10 S11½E 82
- 1977-EARL E. GRAVLIN P.S. 23510 L4 P375 OF SURVEYS  
WEST 20.78' S LEG SIGN POST  
S45E 56.71' STREET SIGN  
N45E 48.12' STEEL COR POST  
N35E 56.03' NAIL IN JUNCTION BOX POST
- 1987-EARL E. GRAVLIN P.S. 23510 L3 P403 OF LCRC ½" HEX BAR  
S45E 56.71' STREET SIGN  
N45E 48.12' STEEL CORNER POST  
N35E 56.03' NAIL IN JUNCTION BOX POST
- 1987-HAROLD N. ELRICH P.S. 18986 L7 P636  
S45E 56.71' STREET SIGN  
N45E 48.12' STEEL CORNER POST  
WEST 25.28' S LEG SIGN  
N45E 59.90' NAIL IN JUNCTION BOX

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998-MICHAEL G. HAY P.S. 41101 FOUND ½" IRON IN MON BOX IN THE CENTER LINE OF BALDWIN AND NEWARK ROAD  
A-9 TO A-8 2652.84' (M)  
A-9 TO A-10 2648.32' (M)  
A-9 TO B-9 2547.34' (M) 2547.03' (R-HBE)  
A-9 TO M-9 102.91' (NORTH)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9 SET STANDARD REMONUMENTATION CAP ON FOUND ½" IRON IN MON BOX  
N40W 97.81' 25" OAK P.K. NAIL E WASHER 17623  
N38E 56.18' POWER POLE P.K. NAIL E WASHER 17623  
S55W 68.60' FENCE POST P.K. NAIL  
N38E 55.40' POWER POLE P.K. NAIL

Signed by Michael G. Hay Date 12-30-98

Surveyor's Michigan License No. 41101

RECEIVED FOR RECORD

99 JAN -6 PM 1:45

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

452

Register of Deeds Stamp & File Number

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

*Michael G. Hay*

9-17-98

