

MAY 28 1997

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 JAN 13 PH 2:52

For corners in

<u>LAPEER</u> <small>County</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>10E</u>	<u>K-13</u>
LAPEER TOWNSHIP	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DeLaugh
 REGISTER OF DEEDS
 LAPEER COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, HAROLD N. ELRICH in a field survey on APRIL 11, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 JOSEPH WAMPLER D.S. SET CORNER POST WHITE OAK 16 N 31° E 70, WHITE OAK 14 N 55° W 209
 1977 BERNARD HENDERSON P.S. #16043 LIBER 004, PAGE 206 - FOUND 1/2" IRON - N 45° W 39.08
 FEET POWER POLE, N 30° E 43.96 FEET 32" OAK, S 45° W 34.23 FEET POWER POLE,
 S 20° E 35.00 FEET 10" PINE (SURVEY)
 1980 LELAND D. BATES P.S. #16699 LIBER 006, PAGES 128 & 129 - N 20° W 35.00 FEET 24" CHERRY,
 S 75° E 42.72 FEET 20" OAK, S 10° E 26.34 FEET 8" CHERRY (SURVEY)
 1980 LELAND D. BATES P.S. #16699 LIBER 004, PAGE 023 - FOUND IRON - N 20° W 35 FEET 24" CHERRY
 S 75° E 42.72 FEET 20" OAK, S 10° E 26.34 FEET 8" CHERRY (LAND CORNER RECORDATION
 CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1996 HAROLD N. ELRICH P.S. #18986 FOUND 1/2" IRON - STARIGHT - AT CENTERLINE OF SUTTON
 ROAD AND WILDER ROAD. FOUND TWO WITNESSES FROM PREVIOUS SURVEYS THAT LOCATE 1/2"
 IRON FOUND.

ACCEPTED 1/2" IRON FOUND AS BEST LOCATION OF ORIGINAL POSITION OF SOUTHWEST CORNER OF SECTION 36, T7N-R10E, LAPEER TOWNSHIP, LAPEER COUNTY, MICHIGAN

MEASURED REFERENCES - K-13 TO L-13 2611.15 FEET
 K-13 TO J-13 2626.34 FEET
 K-13 TO K-12 2644.66 FEET

PEER GROUP
 APPROVED LAND CORNER
 PA 345 OF 1990
 LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR

DATE 8-27-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-13 PLACED LAPEER COUNTY REMONUMENTATION CAP ON 1/2" IRON FOUND

SET NEW WITNESSES - N 20° E 43.96 FEET P.K. NAIL & WASHER IN 30" OAK
 S 40° E 44.14 FEET P.K. NAIL & WASHER IN 10" PINE
 S 45° W 34.23 FEET P.K. NAIL & WASHER IN UTILITY POLE
 N 75° W 51.61 FEET P.K. NAIL & WASHER IN 14" CHERRY

Signed by Harold N. Elrich
 Surveyor's Michigan License No. 18986

Date 12-30-96

