

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

RECEIVED FOR RECORD

94 NOV 18 PM 1:41

## REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 05 PAGE NO. 97  
*Robert DeLoach*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

For corners in  
LAPEER County

Located In: LAPEER TOWNSHIP Corner Code ##

1. Public Land Survey	T <u>7N</u> R <u>10E</u>	M-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, HAROLD N. ELRICH, in a field survey on AUG 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1824 SYLVESTER SIBLEY P.S. SET 1/2 MILE POST - WHITE OAK 30' N 32° W 5 LINKS, IRONWOOD 8" S 79° W 21 LINKS
  - ✓ 1972 HENDERSON, P.S. LIBER 001, PAGE 480 1/2" IRON 54 FEET NORTH OF WEST 1/4 CORNER OF SECTION 19, T7N-R11E, ATTICA TOWNSHIP
  - 1977 HOOTH P.S. LIBER 003, PAGE 298, LAND CORNER RECORDATION CERTIFICATE 1/2" IRON WEST 26.66 FEET 6" CHERRY, S 35° W 60.91 FEET 12" ASH N 15° W 100.88 FEET 12" ASH
  - 1987 ELRICH P.S. LIBER 007, PAGE 618 MONUMENT BOX (NO TIES) MODT PLANS FOUND 1/2" ROD (SAME TIES AS 1977 LAND CORNER RECORDATION CERTIFICATE) EAST 1/4 CORNER IS N 2563.99 FEET FROM SOUTHEAST CORNER & S 2653.83 FEET FROM NORTHEAST CORNER
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 ELRICH P.S. FOUND RAILROAD SPIKE IN MONUMENT BOX AT BRIDGE APPROACH OVER I-69 IN CENTERLINE OF FIVE LAKES ROAD. ORANGE PAINTED CIRCLE ON BRIDGE 53.97 FEET SOUTH OF RAILROAD SPIKE IN MONUMENT BOX. 1972 SURVEY INDICATED 54.00 FEET FROM WEST 1/4 CORNER OF SECTION 19, T7N-R11E, ATTICA TOWNSHIP TO EAST 1/4 CORNER OF SECTION 24, T7N-R10E, LAPEER TOWNSHIP


APPROVED LAND SURVEYOR  
*Harold N. Elrich*  
ACCEPTED RAILROAD SPIKE AS BEST LOCATION OF ORIGINAL POSITION OF EAST 1/4 CORNER OF SECTION 24, T7N-R10E, LAPEER TOWNSHIP

DATE 11-13-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 REPLACED RAILROAD SPIKE WITH 1/2" IRON ROD WITH REMONUMENTATION CAP

NAIL & WASHER IN GUARD RAIL POST N 40° W 33.70 FEET  
NAIL & WASHER IN GUARD RAIL POST N 17° W 85.11 FEET  
NAIL & WASHER IN GUARD RAIL POST N 15° E 121.50 FEET  
NAIL & WASHER IN GUARD RAIL POST N 68° E 23.73 FEET



Signed by *Harold N. Elrich*  
Surveyor's Michigan License No. 18986

Date Nov. 3, 1994