

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:42

LIBER NO. 05 PAGE NO. 98
Robert D. Knight 99

REGISTER OF DEEDS
LANSING, MICHIGAN

For corners in _____
LAPEER County

Located In: LAPEER TOWNSHIP

Corner Code #

1. Public Land Survey	T <u>7N</u> R <u>10E</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, HAROLD N. ELRICH, in a field survey on AUG 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1824 SYLVESTER SIBLEY D.S. SET POST ELM 12" N 62° W 25 LINKS, ELM 20" SOUTH 9 LINKS
 1872 GILBERT BATES SET STONE SUGAR N 49° W 75 LINKS, SUGAR S 52° W 69 LINKS
 1971 BATES P.E. LIBER 001, PAGE 096 1" DIAMETER IRON ROD, 49 FEET NORTH OF CENTERLINE OF NEWARK ROAD - N 30° E 23.45 FEET SOUTHWEST CORNER CONCRETE HEADWALL, N 25° W 40.72 FEET NORTHEAST CORNER CONCRETE HEADWALL, N 45° W 34.72 FEET SOUTHEAST CORNER CONCRETE HEADWALL
 1974 BROWN P.S. LIBER 002, PAGE 645, LAND CORNER RECORDATION CERTIFICATE 5/8" IRON ROD N 71° W 36.19 FEET NAIL IN POWER POLE, N 66° E 26.14 FEET NAIL IN 36" BOX ELDER


(SEE BACK)
 B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 ELRICH P.S. FOUND 5/8" IRON IN CENTERLINE OF FIVE LAKES ROAD AND NEWARK ROAD PROJECTED FROM WEST. CORNER MEASURED 87.74 FEET NORTH OF THE SOUTHWEST CORNER OF SECTION 19, T7N-R11E, ATTICA TOWNSHIP. ORIGINAL GLO NOTES INDICATES 110 LINKS (72.6 FEET) BETWEEN THESE CORNERS. FOUND FOUR WITNESSES FROM PREVIOUS SURVEYS THAT VERIFY POSITION OF 5/8" IRON ROD FOUND.

ACCEPTED 5/8" IRON ROD AS BEST LOCATION OF ORIGINAL POSITION OF SOUTHEAST CORNER OF SECTION 24, T7N-R10E, LAPEER TOWNSHIP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 REMOVED 5/8" ROD AND SET 1/2" IRON ROD WITH STANDARD REMONUMENTATION CAP

NAIL & WASHER 8" BASSWOOD N 40° W 73.95 FEET
 NAIL & WASHER 38" BOX ELDER N 60° E 26.14 FEET
 NAIL & WASHER 6" SCOTCH PINE S 30° E 117.65 FEET
 NAIL & WASHER POWER POLE S 25° W 104.99 FEET



Signed by Harold N. Elrich Date Nov 3, 1994

Surveyor's Michigan License No. 18986

A. (CONTINUED)

1975 HENDERSON P.S. LIBER 003, PAGE 390 FOUND 1" DIAMETER IRON ROD
(SAME TIES AS 1972 SURVEY)

1979 ELRICH P.S. LIBER 005, PAGE 308 FOUND 1" IRON ROD (SAME TIES
AS 1972 & 1975 SURVEYS)


1981 GRAVLIN P.S. LIBER 006, PAGE 254 1/2" IRON (SAME TIES AS PREVIOUS
SURVEYS)

1984 GRAVLIN P.S. LIBER 006, PAGES 653 & 654 87.79 FEET NORTH OF
SOUTHWEST CORNER OF SECTION 19, T7N-R11E, ATTICA TOWNSHIP

1984 ELRICH P.S. LIBER 006, PAGE 825 FOUND 1" IRON ROD (SAME TIES
AS PREVIOUS SURVEYS)

MCOT INDICATES 5/8" ROD - N 66° E 26.14 FEET 36" BOX ELDER,
N 60° W 36.19 FEET TELEPHONE POLE, N 26° E 31.34 FEET
NORTHEAST CORNER CONCRETE HEADWALL

PLANS INDICATE CORNER 87.74 FEET NORTH OF SOUTHWEST CORNER OF
SECTION 19, T7N-R11E, ATTICA TOWNSHIP

APPROVE

RAY G. M. F. D.
DATE 11-13-94

MISC D	9.00
REMLC	P0075
REMOVT	2.00