

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 2:53

LIBER NO. 5 PAGE NO. 22
Melissa Miles
REGISTERED PROFESSIONAL SURVEYOR

For corners in

LAPEER (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>10E</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, HAROLD N. ELRICH in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GLO SURVEY BY JOS. WAMPLER D.S. SET POST CORNER SECTION 25 & 36
IRONWOOD 10" NORTH 4 1/2° WEST 52 LINKS & BEECH 11" SOUTH 86° WEST 35 LINKS
1973 LAND CORNER RECORDATION CERTIFICATE LIBER 002, PAGE 439, FOUND 1/2" IRON, SOUTH 64.83 FEET TO A-11, T7N-R11E BUCKERFIELD P.S. #10868
1973 RECORDED SURVEY LIBER 002, PAGES 555-558 FOUND 1/2" IRON ROD ELRICH P.S. #18986
1973 LAND CORNER RECORDATION CERTIFICATE LIBER 002, PAGE 499 FOUND PIPE SAME THREE WITNESSES AS 1983 SURVEY ELRICH P.S. #18986
1989 RECORDED SURVEY LIBER 008, PAGE 727 FOUND 3/4" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 NOV ELRICH P.S. #18986 FOUND 1/2" PIPE, FOUND TIE SOUTH TO A-11, T7N-R11E, TO BE SAME AS 1973 LAND CORNER RECORDATION CERTIFICATE LIBER 002, PAGE 439 & LAND CORNER RECORDATION CERTIFICATE LIBER 002, PAGE 707, AT INTERSECTION OF HUNTERS CREEK ROAD ON WEST AND CENTERLINE OF FIVE LAKES ROAD

A-11, T7N-R11E, NORTH 64.82 FEET TO M-11, T7N-R10E, SWARTZ P.S. #16945

ACCEPTED FOUND 1/2" PIPE AS BEST EVIDENCE OF ORIGINAL POSITION OF THE NORTHEAST CORNER OF SECTION 36

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 1/2" PIPE WITH REMONUMENTATION CAP

SOUTH 85° EAST 155.79 FEET SET NAIL & REMONUMENTATION TAG IN TRIPLE ELM, 6", 3" & 3"
SOUTH 15° EAST 111.99 FEET SET NAIL & REMONUMENTATION TAG IN 24" MAPLE
SOUTH 50° WEST 76.84 FEET SET NAIL & REMONUMENTATION TAG IN 14" MAPLE
NORTH 20° WEST 134.20 FEET SET NAIL & REMONUMENTATION TAG IN POWER POLE
SOUTH 15.48 FEET FOUND 1/2" PIPE AT INTERSECTION OF CENTERLINE/CENTERLINE OF HUNTERS CREEK & FIVE LAKES ROADS
SOUTH 64.87 FEET FOUND 1/2" PIPE AT A-11, T7N-R11E

Signed by Harold N. Elrich Date 12-1-93
Surveyor's Michigan License No. 18986

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1973
REVISED MAY 14, 1979
REVISED JAN. 1983

