

1993

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 2:55

LIBER 5 PAGE 24

For corners in

LAPEER (County)

Located In:

Corner Code #

- 1. Public Land Survey T 7N R 10E M-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GLO SURVEY BY JOS. WAMPLER D.S. SET CORNER POST ASPIN 9" NORTH 55 1/2° WEST 34 LINKS & ASPIN 8" NORTH 50 1/2° EAST 51 LINKS

1980 LAND CORNER RECORDATION CERTIFICATE

1981 RECORDED SURVEY LIBER 006, PAGES 128 & 129 NO OBJECT STATED BATES P.S. #16699

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 NOV ELRICH P.S. #18986 FOUND 1/2" IRON ROD THREE WITNESS TIES AT INTERSECTION OF FIVE LAKES ROAD & SUTTON ROAD MATCH TIES ON 1981 RECORDED SURVEY. ACCEPTED 1/2" IRON ROD AS BEST EVIDENCE OF ORIGINAL POSITION OF SOUTHEAST CORNER OF SECTION 36

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 1/2" IRON ROD WITH REMONUMENTATION CAP

NORTH 35° EAST 58.08 FEET SET NAIL & REMONUMENTATION TAG IN 36" OAK

SOUTH 40° EAST 53.12 FEET SET NAIL & REMONUMENTATION TAG IN OAK CLUMP 20", 18", 16" & 16"

SOUTH 20° WEST 24.76 FEET SET NAIL & REMONUMENTATION TAG IN TRIPLE OAK

NORTH 65° WEST 61.47 FEET SET NAIL & REMONUMENTATION TAG IN 48" OAK

Signed by Harold N. Elrich

Date 12-1-93

Surveyor's Michigan License No. 18986

