

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 JAN 13 PM 2:53

For corners in

<u>LAPEER</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11E</u>	<u>A-1</u>
	T _____ R _____	_____
ATTICA TOWNSHIP	T _____ R _____	_____
	T _____ R _____	<u>Tag #1</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Melissa De Vough
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH, in a field survey on APRIL 11, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1974 DAVID PAWLACZYK P.S. #17632 - LIBER 002, PAGE 661 (LAND CORNER RECORDATION CERTIFICATE) FOUND 1" REBAR IN MONUMENT BOX - N.W. 50.34 FEET TAG #5826 IN UTILITY POLE, N.E. 49.33 FEET TAG #5825 IN UTILITY POLE, S.E. 72.62 FEET TAG #5824 IN UTILITY POLE, S.W. 72.87 FEET TAG #5827 IN UTILITY POLE
 - 1975 HAROLD N. ELRICH P.S. #18986 - LIBER 003, PAGE 430 (SURVEY) FOUND 5/8" ROD IN MONUMENT BOX - N 45° W 50.35 FEET TELEPHONE POLE, N 45° E 49.33 FEET POWER POLE, S 35° W 72.87 FEET TELEPHONE POLE
 - 1976 BERNARD HENDERSON P.S. #16043 - LIBER 003, PAGE 958 (SURVEY) FOUND IRON-N.W. 50.34 FEET UTILITY POLE, N.E. 49.33 FEET UTILITY POLE, S.E. 72.62 FEET UTILITY POLE, S.W. 72.87 FEET UTILITY POLE

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: (SEE BACK)
- 1996 HAROLD N ELRICH P.S. #18986 FOUND 1/2" IRON WITH REMONUMENTATION CAP IN MONUMENT BOX IN CENTERLINE OF BOWERS ROAD AND FIVE LAKES ROAD. FOUND FOUR WITNESSES FROM PREVIOUS SURVEYS THAT LOCATE THE 1/2" IRON FOUND. CORNER COMMON WITH M-13 T8N-R10E, M-1 T7N-R10E, A-13 T8N-R11E.

ACCEPTED 1/2" IRON WITH REMONUMENTATION CAP AS BEST LOCATION OF ORIGINAL POSITION OF NORTHWEST CORNER OF SECTION 6, T7N-R11E, ATTICA TOWNSHIP, LAPEER COUNTY, MICHIGAN

MEASURED REFERENCES - A-1 TO B-1 2437.09 FEET
A-1 TO A-2 3000.42 FEET
A-1 TO L-1 2607.24 FEET (NORTH 1/4 CORNER, SEC 1, T7N-R10E, LAPEER TWP)
A-1 TO A-12 2638.47 FEET (WEST 1/4 CORNER, SEC. 31, T8N-R11E, ARCADIA TWP)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-1 FOUND LAPEER COUNTY REMONUMENTATION CAP ON 1/2" IRON
 - SET NEW WITNESSES - N 45° W 51.46 FEET P.K. NAIL & WASHER IN POWER POLE
S 35° W 73.00 FEET P.K. NAIL & WASHER IN TELEPHONE POLE
S 30° E 72.60 FEET P.K. NAIL & WASHER IN TELEPHONE POLE
N 40° E 49.34 FEET P.K. NAIL & WASHER IN POWER POLE

Signed by Harold N. Elrich
Surveyor's Michigan License No. 18986



Date 12-30-96

SURVEY &
REMONUMENTATION

MAY 28 1997

COMMISSION

- 1980 HAROLD N. ELRICH P.S. #18986 - LIBER 005, PAGE 710 (SURVEY)
FOUND IRON - SAME WITNESSES AS 1976 SURVEY
- 1981 BERNARD HENDERSON P.S. #16043 - LIBER 008, PAGE 331 (SURVEY)
FOUND IRON IN MONUMENT BOX - N 45° W 50.35 FEET TELEPHONE POLE,
N 45° E 49.33 FEET POWER POLE, S 35° W 72.87 FEET TELEPHONE POLE
- 1993 EARL E. GRAVLIN P.S. #23510 - LIBER 010, PAGE 432 (SURVEY)
NO WITNESSES SHOWN

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LIFEER COUNTY

Ray Davis
RAY DAVIS P.S. CO SURVEYOR
DATE *9-10-96*

MISC D	9.00
REMLC	P0075
REMOVT	2.00