

SURVEY &
REMONUMENTATION

MAR 13 1998

SECTION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

98 FEB 25 PM 3:03

For corners in

| LAPEER | Located In: | Corner Code |
|---------------------------------|--------------------------|----------------|
| Field Land Survey | T <u>7N</u> R <u>11E</u> | A-1 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| Property Controlling in Section | S _____ T _____ R _____ | <u>Seg. #2</u> |
| | S _____ T _____ R _____ | |
| Miscellaneous Property in Sec | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Register of Deeds Stamp & File Number

4 Lot No _____, Recorded Plat _____
5 Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

MICHAEL G. HAY in a field survey on AUGUST, 19 97
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

- 1822 Joseph Wampler set post
- 1877 Gilbert Bates Stone 24,14,6 Small stones Cherry 3 N37E 58, Apple 3 N54E 831/2
- 1974 David d Pawlaczyk P.S. #17632 Liber 2, Page 661, Found 1" rered in mon box,
NW Tag # 5826 in Utility pole 50.34', NE Tag # 5826 in Utility pole 49.33'
SE Tag # 5826 in Utility pole 72.62', SW Tag # 5826 in Utility pole 72.87'
- 1974 David Pawlaczyk P.S. # 17632 Liber 2, Page 884, Found 1" rered in mon box. Witnesses same as above.
- 1975 Harold N. Elrich P.S. # 18986 Liber , Page , Found 5/8" rered in mon box.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Michael G. Hay P.S. # 41101 Found Remon cap in mon box in center line of Bowers and Five Lakes Road. Found four witnesses from previous surveys that locate the remon cap.

- A-1 to A-2 2875.20'
- A-1 to B-1 2437.09'
- A-1 to L-1 2607.24'

Michael G. Hay
10-13-97

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 FOUND LAPEER COUNTY REMONUMENTATION CAP ON 1/2" IRON

- SET NEW WITNESSES - N 45° W 51.46 FEET P.K. NAIL & WASHER IN POWER POLE
- S 35° W 73.00 FEET P.K. NAIL & WASHER IN TELEPHONE POLE
- S 30° E 72.60 FEET P.K. NAIL & WASHER IN TELEPHONE POLE
- N 40° E 49.34 FEET P.K. NAIL & WASHER IN POWER POLE

Signed by Michael G. Hay
Surveyor's Michigan License No. 41101

Date September 26, 1997
LIBER 0006 PAGE 0018

- 1976 Bernard Henderson P.S. # 16043 Liber , Page , Found iron. Witnesses same as above.
1980 Harold N. Elrich P.S. # 18986 Liber , Page , Found iron. Witnesses same as above.
1981 Bernard Henderson P.S. # 18986 Liber , Page , Found iron. Witnesses same as above.
1993 Earl E. Gravlin P.S. # 23510 Liber 10, Page 432, No mention of what found.
1996 Harold N. Elrich P.S. # 18986 Liber 11, Page 709, Found remon cap in mon box.
N 45 W 51.46' Remon tag in pwr. Pole S35W 73.00' Remon tag in tele pole
S30E 72.60' Remon tag in pwr pole N40E 49.34' Remon tag in pwr pole.