

**SURVEY &
REMONUMENTATION**

MAR 13 1998

SECTION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

98 FEB 26 PM 3:07

For corners in

LAPEER

County

Located In:

Corner Code #

1. Public Land Survey	T <u>7N</u> R <u>11E</u>	A-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4 Lot No _____ Recorded Plat _____
5 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

MICHAEL G. HAY in a field survey on AUGUST, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1824 L. Lyons D.S. set post Tamarac 9 N 34 E 30, DO 12 S 59 E 264'
 - 1874 Gilbert Bates C.S. set stake elm 12 N 59½ E 131 elm 20 S 9½ E 214
 - 1972 Robert G. Kay P.S. 14096 L002 P025 N 40 W 65.45' nail T.P. S 70 E 88.48 Nail P. S 50 E 21.70' NW corner bridge abutment
 - 1979 Earl E Gravlin P.S. 23510 L005 P341 surveys S 45 E 88.41" Power Pole N 30 W 64.80' junction box N 60 W 40.21' street sign
 - 1981 Earl E Gravlin P.S. 23510 L006 P064 surveys fnd ½" iron (same wits as 1979 survey above)
 - 1990 Harold N. Elrich P.S. 18986 L008 P850 surveys "x" in top of 6" culvert South end
 - 1993 Harold N. Elrich P.S. 18986 L010 P418 surveys fnd ½" iron bar S 45 E 42.24 "x" in top of 6" culvert south end N 45 E 44.08' north end S 85 E 88.51' nail utility pole (CONTINUED)...
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1997 ROWE ENG. Michael G. Hay P.S. 41101 fnd ½" iron at centerline Five Lakes Road and Peppermill Road. Recovered 3 witnesses indicating that found ½" iron is in the same position as 1993 iron cited above.

A-5 to A-4 2673.84'
A-5 to B-5 2508.77'
A-5 to A-6 2633.27'
A-5 to M-5 (Lapeer) 117.10' NORTH GLO (1.75) 115.50'

Michael G. Hay
10-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 Set standard remon cap on found ½" iron
N 35 W 65.55' "x" NE corner utility riser
S 85 E 88.51' spike in power pole
N 45 E 44.08 "x" in top of 6" culvert south end
S 45 E 42.24' chisel "x" south end 6" culvert

Signed by Michael G. Hay Date September 26, 1997
Surveyor's Michigan License No. 41101