

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 19 AM 11:22

LIBER NO. 05 PAGE NO. 168  
*Hester De Langh 169*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

For corners in	Located In:	Corner Code #
<u>LAPEER</u> <small>County</small>	<u>ATTICA TOWNSHIP</u>	
1. Public Land Survey	T <u>7N</u> R <u>11E</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH in a field survey on NOV 1 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- 1824 LUCIUS LYONS D.S. INTERSECTED WEST BOUNDARY 97 LINKS SOUTH OF POST. SET POST AT INTERSECTION CORNERS TO SECTIONS 18 & 19 - LYNN 13" N 42 1/2° E 26 LINKS, IRONWOOD 8" S 27° E 33 LINKS (SUSPECT 97 LINKS SHOULD BE 79 LINKS)
  - 1972 HENDERSON P.S. LAND CORNER RECORDATION CERTIFICATE - LIBER 001, PAGE 393 SET RAILROAD SPIKE - N 30° E 40.65 FEET ROAD SIGN, S 45° E 30.17 FEET CORNER FENCE POST, N 45° W 48.8 FEET POWER POLE
  - 1975 ELRICH P.S. LIBER 003, PAGE 316 - FOUND RAILROAD SPIKE, N 30° E 40.65 FEET ROAD SIGN, S 45° E 30.17 FEET CORNER FENCE POST, N 45° W 48.8 FEET POWER POLE
  - 1976 HOOTH P.S. LAND CORNER RECORDATION CERTIFICATE LIBER 003, PAGE 299 PLACED 5/8" IRON ROD WITH 1 1/2" DISK STAMPED MDSH&T RLS #14098 - N 45° E 40.17 FEET STEEL ROAD SIGN (OV
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994 ELRICH P.S. FOUND BRASS CAP #14098 RLS (MDSH&T) IN CENTERLINE OF FIVE LAKES ROAD AND CENTERLINE OF GREENWOOD ROAD TO THE EAST. FOUND TWO WITNESSES FROM PREVIOUS SURVEYS WHICH VERIFY THE LOCATION OF THE BRASS CAP WHICH IS SOUTH 48.14 FEET FROM THE SOUTHEAST CORNER OF SECTION 13, T7N-R10E, LAPEER TOWNSHIP, LAPEER COUNTY, MICHIGAN. ORIGINAL GLO MAP INDICATE 79 LINKS (52.14 FEET) BETWEEN THE TWO CORNERS

ACCEPTED 5/8" ROD WITH BRASS CAP AS BEST LOCATION OF ORIGINAL POSITION OF NORTHWEST CORNER OF SECTION 19, T7N-R11E, ATTICA TOWNSHIP, LAPEER COUNTY, MICHIGAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-7 5/8" ROD WITH BRASS CAP - STAMPED #14098 RLS - MDSH&T
- NAIL & WASHER-POWER POWER N 50° W 208.27 FEET
  - NAIL & WASHER-POWER POLE N 10° E 430.15 FEET
  - NAIL & WASHER-POWER POLE N 25° E 152.96 FEET
  - NAIL & WASHER-POWER POLE S 70° E 84.54 FEET

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY  
*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 12-19-94

Signed by Harold N. Elrich Date 12-9-94  
Surveyor's Michigan License No 18986

A. (CONTINUED)

S 45° E 84.49 FEET POWER POLE, S 40° E 30.48 FEET FENCE CORNER  
POST, N 25° W 88.70 FEET TELEPHONE POLE

1984 GRAVLIN P.S. LIBER 006, PAGE 653 - FOUND CORNER 2521.25 FEET  
WEST OF NORTH 1/4 CORNER OF SECTION 19. GOVERNMENT NOTES  
INDICATE DISTANCE IS 2520.54 FEET

1990 BAILEY P.S. LIBER 008, PAGE 992 - FOUND BRASS CAP ON 1/2"  
ROD, NORTH 48.15 FEET 1/2" ROD (NORTHEAST CORNER SECTION 24,  
T7N-R10E, LAPEER TOWNSHIP) S 80° E 84.52 FEET NAIL & TAG IN  
POWER POLE, S 45° E 30.98 FEET NAIL & TAG IN FENCE POST,  
N 45° E 40.45 FEET CENTERLINE ROAD SIGN

1992 ELRICH P.S. LIBER 009, PAGE 864 - FOUND BRASS CAP ON 1/2"  
ROD (SAME TIES AS 1990 SURVEY)

MISC D	9.00
REHLC	PG075
REHONT	2.00