

**SURVEY &  
REMONUMENTATION**

APR 28 1995

**COMMISSION**

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 19 AM 11:31

LIBER NO. 05 PAGE NO. 173  
*Michigan State Survey*  
174  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

For corners in

<u>LAPEER</u> <small>County</small>	Located In: <u>ATTICA TOWNSHIP</u>	Corner Code <u>≠</u>
1. Public Land Survey	T <u>7N</u> R <u>11E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH in a field survey on NOV 11, 19 94  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
6												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1824 LUCIUS LYON D.S. INTERSECTED WEST BOUNDARY LINE 110 LINKS SOUTH OF POST - SET POINT  
AT INTERSECTION CORNER TO SECTIONS 19 & 30 - HICKORY 18" N 26 1/2° E 23 LINKS, ELM 14"  
S 50° E 23 LINKS  
1974 ELRICH P.S. LIBER 003, PAGE 121 - FOUND 1/2" IRON - S 70° W 32.04 FEET NAIL IN POWER  
POLE, N 12° E 103.58 FEET NAIL IN 30" BOX ELDER, S 75° E 31.74 FEET FACE OF ROAD SIGN  
POST, NORTH 39.57 FEET CENTERLINE OF NEWARK ROAD  
1975 ELRICH P.S. LAND CORNER RECORDATION CERTIFICATE LIBER 003, PAGE 081 - FOUND 1/2"  
IRON (SAME TIES AS 1974 SURVEY)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1994 ELRICH P.S. - FOUND 1/2" IRON IN GOOD CONDITION ON LINE WITH THE CENTERLINE OF  
NEWARK ROAD TO THE EAST AND THREE FEET EAST OF THE CENTERLINE OF FIVE LAKES ROAD  
TO THE NORTH AND ON CENTERLINE OF FIVE LAKES ROAD TO THE SOUTH. FOUND IRON IS SOUTH  
87.74 FEET SOUTH OF THE SOUTHEAST CORNER OF SECTION 24, T7N-R10E, LAPEER TOWNSHIP.  
GLO NOTES INDICATE DISTANCE BETWEEN CORNERS IS 110 LINKS (72.60 FEET)

ACCEPTED 1/2" IRON FOUND AS BEST LOCATION OF ORIGINAL POSITION OF THE SOUTHWEST  
CORNER OF SECTION 19, T7N-R11E, ATTICA TOWNSHIP, LAPEER COUNTY, MICHIGAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 PLACED REMONUMENTATION CAP OVER 1/2" IRON ROD  
NAIL & WASHER IN 8" BASSWOOD N 10° W 157.78 FEET  
NAIL & WASHER IN 28" BOX ELDER N 12° E 106.01 FEET  
NAIL & WASHER IN 6" SCOTCH PINE S 82° E 65.35 FEET  
NAIL & WASHER IN POWER POLE S 65° W 31.54 FEET

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY  
*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 12-19-94

Signed by Harold N. Elrich Date 12-9-94  
Surveyor's Michigan License No. 18986

A. (CONTINUED)

1984 GRAVLIN P.S. LIBER 006, PAGE 653 - FOUND CORNER TO BE  
2563.84 FEET WEST OF THE SOUTH 1/4 CORNER OF SECTION 19.  
GOVERNMENT NOTES INDICATE THE DISTANCE AS 2560.14 FEET-  
NO TIES

1984 ELRICH P.S. LIBER 006, PAGE 823 - FOUND 1/2" IRON S 65° W  
32.13 FEET POWER POLE, S 70° E 31.71 FEET ROAD SIGN POST.  
S 25° E 35.54 FEET NORTHEAST CORNER HEADWALL

1984 ELRICH P.S. UNRECORDED SURVEY - FOUND 1/2" IRON (TIES  
SAME AS PREVIOUS SURVEY IN 1984)

1985 BATES P.S. LIBER 006, PAGE 971 - FOUND 1/2" IRON (SAME  
TIES AS 1984 SURVEY)

1992 GRAVLIN P.S. LIBER 009, PAGE 801 - FOUND 1/2" IRON  
S 02°27'34" EAST 87.74 FEET FROM THE SOUTHEAST CORNER OF  
SECTION 24, T7N-R10E, LAPEER TOWNSHIP (SAME TIES AS  
1984 SURVEYS)

STATE HIGHWAY MAPS INDICATE CORNER IS 87.74 FEET SOUTH  
OF THE SOUTHEAST CORNER OF SECTION 24, T7N-R10E, LAPEER  
TOWNSHIP (THE TIES ARE THE SAME AS THE 1984 SURVEYS)

MISC D	9.00
REMLC	P0075
REXONT	2.00