

SURVEY & REMONUMENTATION

MAR 23 2000

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 DEC 14 AM 9:07

For corners in

Lapeer
(County)

Located In:
Attica Township

Corner Code #

- | | | | |
|------------------------------------|---|---|------|
| 1. Public Land Survey | T | R | A-11 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |
4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

Melissa DeVaugh
REGISTERED DEEDS
LAPEER COUNTY MICHIGAN

508

Register of Deeds Stamp & File Number

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 10 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Huston K. Kennedy, in a field survey on August 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1831-GLO Ly, & Sibley, D.S.; No post was set, No witnesses common corner with M-11
1.) 1974-Swarts, PS #16945; LCRC L.002, Pgs.707 & 708 - Fnd a 3/4" Iron Pipe
2.) 1981-Bailey, PS #33968; Survey L.009, Pg.355 - Fnd a 3/4" Rod
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 3/4" Iron Pipe located in the existing centerline of Five Lakes Road extending to the North & South, which has a gravel surface, also 65 feet North of the existing centerline of Hunters Creek Road extending to the East & West, which has a gravel surface. Corner common to Sections 25 & 36, T7N, R10E, Lapeer Township (M-11) is located 64.83 feet to the North. A-11 as found is 0.63 feet East of the range line.

Witnesses from LCRC #1 & Survey #2 were used to recover and verify the location of the found 3/4" Iron Pipe.

I accepted the found 3/4" Iron Pipe as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-11 to A-10
No GLO
No recorded distances
2641.52 Ft. (MEA 1999)

A-11 to M-11
Common Corner
No recorded distances
64.83 Ft. (MEA 1999)

A-11 to A-12
No GLO
No recorded distances
2641.15 Ft. (MEA 1999)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-11 I replaced the found 3/4" Iron Pipe with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped
Remonumentation #17623
N53°E 165.16' Set Mag Nail & Remon Washer South face 14" Elm
N47°W 131.76' Set Mag Nail & Remon Washer SW face 12" Maple
S15°E 168.18' Set Mag Nail & Remon Washer North face 31" Oak
S70°E 51.72' Set Mag Nail & Remon Washer North face 5" Ash
North 64.83' corner common to Sections 25 & 36, T7N, R10E, Lapeer Township (M-11)

APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY
RAY DAVIS P.S. CO. SURVEYS
DATE 10-21-99

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 11-22-99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995