

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
99 JAN -6 PM 1:23

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

442

Register of Deeds Stamp & File Number

For corners in

<u>LAPEER</u> (County)	Located in: ATTICA TWP	Corner Code # K-13
1. Public Land Survey	T <u>7N</u> R <u>11E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Shelby W Money, in a field survey on October 8

19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816-GLO Wampler, Set a Post on twp line common to sections 35 and 36.

- L5, Pg 330, October 1978 survey by Kay Engineering, Found 1/2" iron.
- L5, Pg 267, April 1979 survey by Henderson Bates, Found iron.
- L7, Pg 173, October 1985 survey by Earl Gravlin, Found 1/2" iron.
- L7, Pg 216, January 1986 survey by Kobs-King & Associates, Found iron.
- L2, Pg 709, October 1974 LCRC by Stephen Swarts, Set iron from witnesses of Kay Engineering.
- L3, Pg 513, April 1979 LCRC by Harold Elrich, Found 1/2" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron is in physical centerline of Sutton Road, which has a gravel surface and runs east and west. Corner is 6' east of centerline of Winslow Road which extends to the north and also has a gravel surface. The following witness was found:

- S 60° W 41.50' Nail & Tag in utility pole. Measure 41.58'. L2, Pg709

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Placed 2" diameter brass cap stamped LAPEER COUNTY REMONUMENTATION, PS#30092 on found 1/2" iron.

- Az 40° 43.47' to centerline of the Brass Disk set in a USGS BM stamped TT22B, 1942 located in 0.6' square concrete monument.
- Az 100° 155.13' to P. K. nail found in southwest face of utility pole.
- Az 115° 165.59' to P. K. & Lapeer County Remon Tag set in the north face of a utility pole w/transformer.
- Az 235° 41.58' to P. K. nail found in southwest face of a utility pole.
- Az 325° 53.30' to a chisel mark in top west end of a 18"

FIELD MEASUREMENTS

K-13 TO J-13 2631.42' GLO 2640.00'

K-13 TO L-13 2618.42' GLO 2640.00'

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 12/20/98
Surveyor's Michigan License No. 30092



RAY DAVIS P.S. CC, SURVEYOR
DATE 10-13-98

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		34		
13													

A