

MAR 29 1999

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER
(County)

Located In:
ATTICA TWP

Corner Code, #

- 1. Public Land Survey T 7N R 11E L-13
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

RECEIVED FOR RECORD

99 JAN -6 PM 1:38

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

443

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Shelby W Money, in a field survey on October 8, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816-GLO Wampler, Set a 1/2 Mile Post on twp line 40 chains east of southwest corner of section 36.

- 1. L5, Pg 748, June 1978 survey by Henderson Bates, Found 1/2" rod.
- 2. L5, Pg 267, April 1979 survey by Henderson Bates, Found 1/2" iron.
- 3. L7, Pg 216, January 1986 survey by Kobs-King & Associates, Found iron.
- 4. L2, Pg 703, November 1974 LCRC by Stephen Swarts, Set iron midway between Southwest and Southeast corners of section 36.
- 5. L3, Pg 513, April 1979 LCRC by Harold Elrich, Found 1/2" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron is 4' north of physical centerline of Sutton Road, which has a gravel surface and runs east and west. The following witnesses were found:

- 1. P. K. nail in power pole N.N.W. 50.37 L7, Pg 216. Measure 50.37'.
- 2. P. K. nail in power pole W.S.W. 165.782, L7, Pg 216. Measure 165.98'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


L-13 Replaced bent iron with 1/2" iron and placed 2" diameter brass cap stamped LAPEER COUNTY REMONUMENTATION, PS#30092 on 1/2" iron.

- 1. Az 110° 108.80' to P. K. nail found in north face of utility pole.
- 2. Az 200° 27.97' to P. K. nail found in east face of utility pole.
- 3. Az 270° 165.98' to P. K. nail found in north face of utility pole..
- 4. Az 295° 94.91' to P. K. with LAPEER COUNTY REMON TAG set in south face of a 8" red maple.
- 5. Az 355° 50.35' to P. K. nail found in west face of utility pole.

FIELD MEASUREMENTS L-13 TO K-13 2618.42' GLO 2640.00 L-13 TO M-13 2618.36' GLO 2640.00
L-13 TO M-1 (T7N, R6E) 1907.07 GLO 1914.00

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Shelby W Money Date 12/30/98
Surveyor's Michigan License No. 30092



APPROVED LAND CORNER GROUP
LAPEER COUNTY
DATE 10-13-98