

**SURVEY &  
REMONUMENTATION**

MAR 13 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
ATTICA TOWNSHIP**

RECEIVED FOR RECORD  
98 JAN -7 PM 2:54

For corners in

LAPEER  
(County)

Located In:

Corner Code #

- |                                    |       |                     |            |
|------------------------------------|-------|---------------------|------------|
| 1. Public Land Survey              |       | <u>T 7 N R 11 E</u> | <u>M-1</u> |
|                                    |       | T ___ R ___         | _____      |
|                                    |       | T ___ R ___         | _____      |
|                                    |       | T ___ R ___         | _____      |
| 2. Property Controlling in Section | S ___ | T ___ R ___         | _____      |
|                                    | S ___ | T ___ R ___         | _____      |
| 3. Miscellaneous Property in Sec.  | S ___ | T ___ R ___         | _____      |
|                                    | S ___ | T ___ R ___         | _____      |

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WILLIAM E. SODERBERG, in a field survey on May 7, 19 97 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- |                    |                        |            |   |
|--------------------|------------------------|------------|---|
| 1. GLO 1816        | Joseph Wampler         | Set post   | No witnesses remain   |
| 2. Survey 5/18/84  | R. Kay #14096          | L6, P.704  | Found 1/2" Iron M-1 Attica  |
| 3. Survey 8/30/88  | L. Bates #16699        | L.8, P.31  | Found 1/2" Iron M-1 Attica  |
| 4. Survey 2/20/89  | H. Elrich #18986       | L.8, P.326 | Found 1/2" Iron M-1 Attica  |
| 5. Survey 11/13/91 | H. Elrich #18986       | L.9, P.591 | Found 1/2" Iron M-1 Attica  |
| 6. Survey 2/17/92  | H. Elrich #18986       | L.9, P.783 | Found 5/8" Iron in mon box M-1 Attica                                   |
| 7. LCRC 1/5/94     | J. Niederhauser #24608 |            | Set Brass Remon disk in existing monument box for M-13 Arcadia Township |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a standard lapeer County Remon cap stamped M-13 #24608 in monument box 4" below the surface of asphalt road. The corner is in the centerline of Bowers Road (asphalt) East and West and Summers Road (gravel) to the North and South

The found corner is Common with M-13 Arcadia T.8N.,R11E.; A-1 Imlay Township T.7N.,R12E. And A-13 Goodland Township T.8N.,R12E.

Witness found: From items 2, 3, 4 and 5, S.30° E 61.98' Nail in fence post  
From item 6 S.30°E. 60.90 PK nail in corner fence post  
From item 7 NW 114.96' nail/remon tag in East face 6" Birch  
NE 129.88 nail/remon tag in West face 6" Ash  
SE 61.00 nail/remon tag in West face fence post

Distances: M-1 to M-2 2881.50

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


We placed a standard Lapeer County Remonumentation Brass cap on the found 1/2" rebar stamped #17635 as the best location for this corner as accepted by the Professional Surveyors in this area.

- |           |         |  |
|-----------|---------|--|
| N. 25° W. | 114.96' | Set PK/Lapeer County remon tag in East face 6" Birch |
| N. 20° E. | 129.88' | Found PK/Lapeer County remon tag in West face 6" Ash |
| S. 15° E. | 99.27'  | Set PK/Lapeer County remon tag in West face 36" Oak  |
| S. 45° W. | 183.17' | Northeast corner House                               |

Signed by William E. Soderberg Date December 16, 1997  
Surveyor's Michigan License No. 17635

FEB GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 10-13-97



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983