

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 ATTICA TOWNSHIP

RECEIVED FOR RECORD
98 JAN -7 PM 2: 56

For corners in

LAPEER	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>7</u> N R <u>11</u> E	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DaVough
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, WILLIAM E. SODERBERG, in a field survey on May 7, 19 97 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|-------------------|------------------|------------------------------|
| 1. GLO 1822 | Joseph Wampler | Set post No witnesses remain |
| 2. Survey 7/28/74 | R. Kay #14096 | L3, P.702 Found 1/2" Iron |
| 3. LCRC 6/18/90 | J. Bailey #33966 | L.4, P.341 Found 1/2" Iron |
| 4. Survey 6/1/90 | J. Bailey #33966 | L.8, P.874 Found 1/2" Iron |
| 5. Survey 2/1/94 | L. Bates #16699 | L.10, P.680 Found 1/2" Iron |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set a PK in the North asphalt apron of Summers Road North and South from witnesses. Position in on the extension of Old M-21 from the West and the centerline of Summers Road

Witness found: From items 3 and 4 South 59.00 Monument box; N.20°E. 65.54' PK nail in PP; East 33.73' Mdot nail/tag in PP S.45°E. 63.73' Nail and tag on PP.
From item 5 South 59.00 monument box; S.60°E. 64.18' TP

Distances: M-2 to M-3 2668.23 feet GLO 40 chs M-3 to A-3 Imlay 59.00 feet
M-3 to M-4 2667.31 feet GLO 40 chs

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

We placed a standard Lapeer County Remonumentation Brass cap in a new monument box set by the Lapeer County Road Commission at this location stamped #17635 as the best location for this corner as accepted by the Professional Surveyors in this area.

- | | | |
|-----------|--------|---|
| East | 19.00 | Back concrete curb |
| N. 30° E. | 66.06' | Found nail/MDOT tag in Southeast face utility pole |
| S. 75° E. | 33.81 | found nail/MDOT tag in Northeast face utility pole |
| S. 65° E. | 63.62' | Found nail/MDOT tag West face utility pole |
| South | 59.00' | Standard Lapeer County Remon Brass disk in monument box A-3 Imlay |
| N. 85° W. | 177.45 | Set PK/Lapeer County Remon tag in South face utility pole |

Signed by *William E. Soderberg* Date December 15, 1997
Surveyor's Michigan License No. 17635

FIELD GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

DAVID P. S. CO. SURVEYOR
10-12-97



APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983