

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
ATTICA TOWNSHIP

RECEIVED FOR RECORD  
98 JAN -7 PM 2:58

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 7 N R 11 E</u>	<u>M-5</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, WILLIAM E. SODERBERG, in a field survey on May 7, 19 97 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1822 Joseph Wampler Set post No witnesses remain

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" rebar/cap 17635 2' West of the centerline of Summers Road (asphalt) North and South and the centerline of Attica Road (asphalt) to the West.

Distances: M-4 to M-5 2666.58 feet GLO 40 chs M-5 to A-5 lmlay 16.90 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

We placed a standard Lapeer County Remonumentation Brass cap in a new monument box set by the Lapeer County Road Commission stamped #17635 as the best location for this corner as accepted by the Professional Surveyors in this area.

N. 75° W. 157.07' Set PK/Lapeer County Remon tag in South face utility pole  
N. 20° E. 120.15' Set pk/Lapeer County Remon tag in West face 40" Oak  
S. 30° E. 73.28' Set PK/Lapeer County Remon tag in West face clump of 4" Poplars  
South 16.90' Found a Standard Lapeer County Remon Brass disk A-5 lmlay in a monument box

Signed by William E. Soderberg Date November 18, 1997

Surveyor's Michigan License No. 17635

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

SEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY



RAY DAVIS P.S. CO. SURVEYOR  
DATE 10-13-97

LIBER 0006 PAGE 0008