

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER Located In: ATTICA TOWNSHIP Corner Code #
(County)

1. Public Land Survey T 7N R 11E M-6
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

RECEIVED FOR RECORD

94 DEC -9 PM 3:13
LIBER NO. 05 PAGE NO. 139
Melissa D. Smith
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on SEPTEMBER 2, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	1822	PAGE 379	JOSEPH WAMPLER	SET POST	NO WITNESSES FOUND
SURVEY	1971	LIBER 001 PAGE 075	BERNARD HENDERSON, #16043	FOUND,	UNKNOWN
WITNESS	1977	UNRECORDED	LAPEER COUNTY ROAD COMMISSION	FOUND,	UNKNOWN
SURVEY	1977	LIBER 004 PAGE 255	HAROLD N. ERLICH, #18986	FOUND,	PK'NAIL

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND, 1/2" REROD WITH CAP #33699/J. BAILEY, IN SEALCOAT ROAD

SURVEY	1971	LIBER 001 PAGE 075	FOUND,	UNKNOWN
		N 45° W 94.78'	FOUND,	CORNER OF HOUSE
		S 85° W 75.61'	FOUND,	POWER POLE
LCRC WITNESS	1977	UNRECORDED	FOUND,	UNKNOWN
		S 45° W 47.07'±	FOUND,	TELEPHONE POLE
		S 50° E 82.38'	FOUND,	TELEPHONE POLE

M-6 TO M-5 T.7N., R.11E. G.L.O. 40 CHAINS MEASURE 2666.13'
M-6 TO M-7 T.7N., R.11E. G.L.O. 40 CHAINS MEASURE 2650.56'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET, BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED #30092 / M-6 ON A 1/2" X 18" REBAR IN A MONUMENT BOX SET BY THE LAPEER COUNTY ROAD COMMISSION

AZIMUTH	120°	82.97'	SET,	NAIL W/LAPEER TAG IN THE NORTH FACE OF A UTILITY POLE
AZIMUTH	225°	45.96'	SET,	NAIL W/LAPEER TAG IN THE NORTH FACE OF A UTILITY POLE
AZIMUTH	270°	64.30'	SET,	NAIL W/LAPEER TAG IN THE SOUTH FACE OF A UTILITY POLE
AZIMUTH	310°	111.50'	FOUND,	THE NORTHEAST CORNER OF A HOUSE AT STREET ADDRESS #47 NORTH SUMMERS ROAD
AZIMUTH	180°	19.60'	FOUND,	TO A-7, T.7N., T.12E. /IMLAY TOWNSHIP

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Signed by Shelby W. Money Date December 2, 1994
Surveyor's Michigan License No. 30092 RAY DAVIS, P.E., CO. SURVEYOR
DATE 12-9-94