

# SURVEY & REMONUMENTATION

APR 28 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
	ATTICA TOWNSHIP	
1. Public Land Survey	T <u>7N</u> R <u>11E</u>	<u>M-7</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

RECEIVED FOR RECORD  
94 DEC -9 PM 3:12  
LIBER NO. 05 PAGE NO. 138  
*Melba J. Vaughn*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, SHELBY W. MONEY, in a field survey on SEPTEMBER 2, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- |                                   |          |                               |                              |
|-----------------------------------|----------|-------------------------------|------------------------------|
| 1) G.L.O. 1822                    | PAGE 379 | JOSEPH WAMPLER                | SET POST, NO WITNESSES FOUND |
| 2) WITNESS 1986 UNRECORDED        |          | LAPEER COUNTY ROAD COMMISSION | FOUND, 1/2" IRON             |
| 3) WITNESS 1988 UNRECORDED        |          | LAPEER COUNTY ROAD COMMISSION | FOUND, UNKNOWN               |
| 4) LCRC 1973 LIBER 002 PAGE 233   |          | BERNARD HENDERSON, #16043     | SET, 1/2" IRON               |
| 5) LCRC 1974 LIBER 002 PAGE 577   |          | HERBERT J. KOBBS, #14097      | FOUND, 5/8" BAR              |
| 6) LCRC 1986 LIBER 004 PAGE 117   |          | BERNARD HENDERSON, #16043     | FOUND, 1/2" IRON             |
| 7) SURVEY 1974 LIBER 002 PAGE 713 |          | HERBERT J. KOBBS, #14097      | FOUND, 5/8" IRON BAR         |
| 8) SURVEY 1985 LIBER 006 PAGE 930 |          | EARL E. GAVIN, #23510         | FOUND, 1/2" IRON             |
| 9) SURVEY 1986 LIBER 007 PAGE 456 |          | BERNARD HENDERSON, #16043     | FOUND, 1/2" IRON             |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND, 1/2" REBAR IN GRAVEL ROAD BELLE RIVER ROAD TO THE WEST AND SUMMERS ROAD NORTH AND SOUTH
- WITNESSES FOUND REFERENCING ITEMS 2, 3 AND 6  
S 70° E 47.63' FOUND, 10" CEDAR
- WITNESSES FOUND REFERENCING ITEMS 4, 7 AND 8  
S 60° E 29.06' FOUND, 12" ASH  
N 30° W 74.48' FOUND, POWER POLE
- WITNESSES FOUND REFERENCING ITEMS 5  
NORTHWEST 74.26' FOUND, NAIL AND WASHER IN A POWER POLE  
SOUTHWEST 46.12' FOUND, NAIL AND WASHER IN A POWER POLE
- WITNESSES FOUND REFERENCING ITEMS 9  
S 70° E 47.63' FOUND, 10" CEDAR  
S 50° E 50.55' FOUND, 4" CEDAR  
N 45° W 59.27' FOUND, CORNER FENCE POST
- M-7 TO M-6 T.7N., R.11E. G.L.O. 40 CHAINS MEASURE 2650.56'  
M-7 TO M-8 T.7N., R.11E. G.L.O. 40 CHAINS MEASURE 2660.80'



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- FOUND, 1/2" REROD  
SET, BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED #30092 / M-7 ON A 1/2" X 18" REBAR  
AZIMUTH 25° 39.60' SET, "X" ON THE EAST END OF AN 18" C.M.P., 40± NORTH OF BELLE RIVER ROAD  
AZIMUTH 120° 47.62' SET, NAIL W/LAPEER TAG IN THE SOUTHWEST FACE OF A 12" CEDAR  
AZIMUTH 315° 50.78' SET, "X" ON THE WEST END OF AN 18" C.M.P., 40± NORTH OF BELLE RIVER ROAD  
AZIMUTH 345° 72.47' SET, NAIL W/LAPEER TAG IN THE NORTHEAST FACE OF A UTILITY POLE  
AZIMUTH 180° 21.20' FOUND, 1/2" REBAR } A-7, T.7N., R.12E. / IMLAY TOWNSHIP

Signed by *Shelby W. Money* Date December 2, 1994  
Surveyor's Michigan License No. 30092

RAY DAVIS, P.S. CO. SURVEYOR  
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
DATE 12-9-94 REVISED MAY 14, 1975  
REVISION JAN. 1983