

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER Located in: Corner Code #
(County) ATTICA TOWNSHIP

1. Public Land Survey T 7N, R 11E M-8
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

RECEIVED FOR RECORD

94 DEC -9 PH 3:11

LIBER NO. 15 PAGE NO. 137

Melbae D. Stang

REGISTRAR OF DEEDS
LAPEER COUNTY, MICHIGAN

Registrar of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on SEPTEMBER 2, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1) G.L.O.	1822	PAGE 379	JOSEPH WAMPLER	SET POST	NO WITNESSES FOUND
2) WITNESS	1987	UNRECORDED	LAPEER COUNTY ROAD COMMISSION		FOUND, UNKNOWN
3) LCRC	1986	LIBER 004 PAGE 117	BERNARD HENDERSON, #16043		FOUND, 1/2" IRON
4) SURVEY	1987	LIBER 007 PAGE 486	BERNARD HENDERSON, #16043		FOUND, 1/2" IRON BAR
5) SURVEY	1987	LIBER 007 PAGE 592	BERNARD HENDERSON, #16043		FOUND, 1/2" IRON
6) SURVEY	1991	LIBER 009 PAGE 230	HAROLD N. ERLICH, #18986		FOUND, 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND, 1/2" REBAR IN GRAVEL ROAD, NORTH, SOUTH AND WEST
FENCE LINE TO THE EAST / FENCE RIGHT-OF-WAY - STONE AND STUMPS 10± WIDE

WITNESSES FOUND REFERENCING ITEMS 2, 3, 4, 5 AND 6

N 75° E	21.45'	FOUND, 18" CHERRY
EAST	40.35'	FOUND, 3" MAPLE
S 30° W	56.25'	FOUND, TELEPHONE POLE
S 50° W	51.07'	FOUND, 20" CHERRY

M-8 TO M-7	T.7N., R.11E.	G.L.O. 40 CHAINS	MEASURED 2680.80'
M-8 TO M-9	T.7N., R.11E.	G.L.O. 40 CHAINS	MEASURED 2685.00'

COMMON CORNER TO A-8, T.7N., R.12E. / IMLAY TOWNSHIP



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET, BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED #30092 / M-8
ON A 1/2" X 18" REBAR

AZIMUTH 70°	21.44'	SET, NAIL W/LAPEER TAG IN THE NORTH FACE OF AN 18" CHERRY
AZIMUTH 90°	40.40'	SET, NAIL W/LAPEER TAG IN THE NORTH FACE OF AN 8" OAK
AZIMUTH 210°	56.18'	SET, NAIL W/LAPEER TAG IN THE WEST FACE OF A UTILITY POLE
AZIMUTH 250°	50.87'	SET, NAIL W/LAPEER TAG IN THE NORTH FACE OF AN 18" CHERRY

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Signed by *Shelby W. Money* Date December 2, 1994

Surveyor's Michigan License No. 30092

RAY DAVIS & SONS, CO. SURVEYOR
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JUL 26, 1971
DATE 12/9-94 REVISED MAY 14, 1978 REVISED JAN, 1983