

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located in:	Corner Code #
	ATTICA TOWNSHIP	
1. Public Land Survey	T <u>7N</u> R <u>11E</u>	<u>M-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED FOR RECORD

94 DEC -9 PM 3:10
LIBER NO. 65 PAGE NO. 136
Melissa DeLoach
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on SEPTEMBER 2, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	1822	PAGE 378	JOSEPH WAMPLER	SET POST, NO WITNESSES FOUND
WITNESS	1919	UNRECORDED	LAPEER COUNTY ROAD COMMISSION	FOUND, CORNERSTONE
LCRC	1973	LIBER 003 PAGE 273	PLAN FOR NEWARK ROAD / COUNTY ROAD #58	SET, 5/8" ROD WITH MDSH DISC IN MONUMENT BOX
			DOUGLAS W. HOOTH, #7966	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND, 5/8" REBAR WITH 1/2" MDSH CAP IN A MONUMENT BOX CENTERLINE OF AN ASPHALT ROAD TO THE WEST

THIS CORNER VERIFIED BY:
LCRC WITNESS 1977 UNRECORDED
S 15° E 76.55' FOUND, MDSH TAG ON A 21" MAPLE

M-9 TO M-8,	T.7N., R.11E. G.L.O. 40 CHAINS	MEASURE 2665.00'
M-9 TO M-10,	T.7N., R.11E. G.L.O. 40 CHAINS	MEASURE 2658.12'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND, 5/8" ROD WITH 1/2" MDSH DISC IN A MONUMENT BOX. LEFT IN PLACE

AZIMUTH	10°	229.30'	SET, NAIL W/LAPEER COUNTY TAG IN THE WEST FACE OF A UTILITY POLE
AZIMUTH	95°	180.87'	FOUND, PK'NAIL "AND" SET NAIL WITH LAPEER COUNTY TAG IN THE NORTH FACE OF A UTILITY POLE
AZIMUTH	150°	76.46'	FOUND, DOUBLE HEADED NAIL W/MDSH TAG IN THE SOUTHWEST FACE OF A 20" OAK
AZIMUTH	355°	144.30'	FOUND, DOUBLE HEADED NAIL W/MDSH TAG IN THE EAST FACE OF A UTILITY POLE
AZIMUTH	00°	30.90'	FOUND, IRON W/BRASS CAP IN MONUMENT BOX: A-9 T.7N., R.12E., IMLAY TOWNSHIP

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Signed by *Shelby W. Money* Date December 2, 1994
Surveyor's Michigan License No. 30092

RAY DAVIS P.S. CO. SURVEYOR

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED 10/11/88
REVISED JAN. 1983