

SURVEY & REMONUMENTATION

1993

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 2:39

LIBER NO. 5 PAGE NO. 4

Melissa Miles  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

For corners in  
COMMISSION  
LAPEER  
(County)

Located In: Corner Code #  
Attica Township

- 1. Public Land Survey T 7N R 11E M-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	4		3		2		1			
3													
4	7		8	9		10		11		12			
5													
6	18		17	16		15		14		13			
7													
8	19		20	21		22		23		24			
9													
10	30		29	28		27		26		25			
11													
12	31		32	33		34		35		36			
13													

I, Shelby W. Money, in a field survey on September 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Post G.L.O. notes page 374 and 376
- L.C.R.C. L.2 P.701 by Swarts (1974) 1/2" rod in concrete
- L.C.R.C. L.3 P.449 by Henderson (1978) 1/2" rod in concrete

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 1/2" rebar, in ravine on the east side fo Summers Road on projected centerline of Sutton Road to the west
- East 26'+ to locust tree (no nail)
- Southwest 5'+ to locust tree (no nail)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- N 80° E 26.50' Set Lapeer tag/nail in the north face of " Locust tree
- S 25° W 5.00' Set Lapeer tag/nail in the northwest face of a 21" Locust tree
- S 10° W 101.12' Set Lapeer tag/nail in the east face of 12" Elm tree
- East 8.0' to the west face of fence post
- West 24.0'+ to the edge of gravel

SET LAPEER COUNTY REMONUMENTATION BRASS CAP MARKED 30092 / M-13 OVER EXISTING IRON



Signed by Shelby W. Money  
Surveyor's Michigan License No. 30092

Date December 21, 1993