

MAR 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
IMLAY TOWNSHIP

RECEIVED FOR RECORD
98 JAN -7 PM 3:00

For corners in

LAPEER

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 7 N R 12 E A-2
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, WILLIAM E. SODERBERG, in a field survey on May 7, 19 97 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

No GLO for this corner

No surveys or LCRC recorded for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A good solid fence line runs East along the East and West Quarter Line for occupation. We ran 2000' of this fence and projected to intersect the line between M-2 and M-3 Attica Township and set the corner position by this occupation fence. On the centerline of Summers Road (gravel) North and South.

The Set corner is 77.00 feet South of M-2 Attica.

Distances: A-1 to A-2 2958.50 feet A-2 to A-3 2650.31 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

We placed a standard Lapeer County Remonumentation Brass cap on the set 1/2" rebar stamped #17635 as the best location for this corner as accepted by the Professional Surveyors in this area.

- N. 25° E. 95.12' Set PK/Lapeer County remon tag in Northwest face utility pole
- N. 55° E. 30.83' Notch East end 18" culvert
- N. 40° W. 28.38' Notch West end 18" culvert
- North 77.00' Standard Lapeer County Remon Brass disk for M-2 Attica

Signed by William E. Soderberg Date November 18, 1997
Surveyor's Michigan License No. 17635

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974
REVISED MAY 14, 1976
REVISED JAN., 1983

LAPEER COUNTY
PROTECTED LAND CORNER
20,045 OF 1990
LAPEER COUNTY
William E. Soderberg
WILLIAM E. SODERBERG
LAND SURVEYOR
DATE 10-13-97

