

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 IMLAY TOWNSHIP

RECEIVED FOR RECORD
 98 JAN -7 PM 3:01

For corners in

LAPEER
 (County)

Located In: Corner Code #

- | | | | |
|------------------------------------|---------------|-----------------------------|-------------|
| 1. Public Land Survey | | <u>T 7 N R 12 E</u> | <u>A-3</u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |

Melissa DaVough
 REGISTER OF DEEDS
 LAPEER COUNTY MICHIGAN
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, WILLIAM E. SODERBERG, in a field survey on May 7, 19 97 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|-------------------|---------------------------------------|--------------------|
| GLO 1824 | L. Lyons set post. No witnesses found | |
| 1. Survey 4/26/72 | R. Kay #14096 | L. 1, P. 420 |
| 2. LCRC 2/15/89 | E. Gravlin #23510 | L. 4, P. 230 |
| | | Unknown |
| | | Found monument box |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a monument box in the centerline of Summers Road (gravel) North and South and on the Easterly extension of Imlay City road to the East. Monument box is in a curve on Old M-21. Top was rusted on, we made a hole in the top and found a 5/8" Iron.

We found no old witnesses from recorded information.

Distances: A-3 to A-4 2640.67 feet A-2 to A-3 2650.31 feet
 A-3 to M-3 Attica Township 59.00 feet GLO 90 links or 59.40 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


We placed a standard Lapeer County Remonumentation Brass cap on the found 5/8" Iron in the existing monument box stamped #17635 as the best location for this corner as accepted by the Professional Surveyors in this area.

- N. 25° E. 121.52' Found nail/MDOT tag in Southeast face utility pole
- N. 35° E. 67.47' Found nail/MDOT tag in Southeast face utility pole
- N. 65° E 69.28' Found nail/MDOT tag in Southeast face utility pole
- N. 65°W. 187.60' Set PK/Lapeer County Remon tag in South face utility pole
- North 59.00' Standard Lapeer County Remon Brass disk for M-3 Attica

Signed by William E. Soderberg Date December 15, 1997
 Surveyor's Michigan License No. 17635

LAPEER GROUP
 APPROVED LAND CORNER
 PA 345 OF 1990
 LAPEER COUNTY

 RAY CAVIS P.S. CC. SURVEYOR
 DATE 10-13-97



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983