

**SURVEY &
REMONUMENTATION**

MAR 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
IMLAY TOWNSHIP**

RECEIVED FOR RECORD

98 JAN -7 PM 3:03

For corners in

Lapeer
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|---------------|-----------------------------|-------------|
| 1. Public Land Survey | | <u>T 7 N R 12 E</u> | <u>A-4</u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |

Melissa DeVaugh
**REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, WILLIAM E. SODERBERG, in a field survey on May 7, 19 97 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

No GLO for this corner

1. Survey 11/20/73 R. Kay #14096 L. 2, P. 453 Unknown

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1/2" rebar in the centerline of Summers Road (gravel) North and South. No occupation to the East.

Witnesses found:
N. 40°W. 43.6' Cor. Post.

Distances: A-3 to A-4 2640.67 feet A-42 to A-5 2651.03 feet
A-4 to M-4 Attica Township 32.45 feet

**PEER GROUP
APPROVED LAND CORNER
REGISTER OF 1990
LAPEER COUNTY**

William E. Soderberg
**WILLIAM E. SODERBERG
PROFESSIONAL SURVEYOR
No. 17635**

DATE: 10-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

We placed a standard Lapeer County Remonumentation Brass cap on the found 1/2" Iron stamped #17635 as the best location for this corner as accepted by the Professional Surveyors in this area.

- N. 25° E. 76.25' Set PK/Lapeer County Remon tag in Northwest face 10" Elm
- N. 75° E. 26.82' Set PK/Lapeer County Remon tag in Southwest face 10" Poplar
- N. 85° W. 25.62' Set PK/Lapeer County Remon tag in Southeast face 10" Poplar
- N. 10°W. 100.18' Set PK/Lapeer County Remon tag in Southwest face 10" Ash
- North 32.45' Standard Lapeer County Remon Brass disk for M-4 Attica
- East 33.00 Found Iron/cap #23510



Signed by William E. Soderberg Date December 15, 1997
Surveyor's Michigan License No. 17635