

SURVEY & REMONUMENTATION

APR 29 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 NOV 22 PM 4:05

LIBER NO. 005, PAGE NO. 309

Nelson D. Haugh

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
	IMLAY TOWNSHIP	
1. Public Land Survey	T <u>7N</u> R <u>12E</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on May 19, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | | |
|--------------|------|-------------------|-------------------------------|----------|--------------------|
| 1) G.L.O. | 1824 | Page 591 | Lucius Lyon | Set Post | No witnesses found |
| 2) Survey | 1978 | Liber 4, Page 733 | Robert G. Kay, #14096 | Found | Railroad Spike |
| 3) Witnesses | 1978 | | Lapeer County Road Commission | Found | Railroad Spike |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Railroad Spike in centerline of Summers Road and on fence line to East.

Found witnesses: Items 2 & 3: S 35° E 60.11 Nail 8" Maple

Distance: A-5 to M-5 (T7N, R11E) North 16.80' Measured
A-5 to A-6 South 2669.0' measured, 2669.24 Kay record
A-5 to M-6 (T. 7 N., R. 11 E.) South 2649.33' measured

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY
Ray D. Money
RAY D. MONEY P.S. CO. SURVEYOR
DATE 7-13-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a Brass Lapeer County Remonumentation Cap stamped A-5; 30092 on a 1/2" by 18" rebar in a monument box set by the Lapeer County Road Commission.

- 15° 136.75' Set PK/Lapeer County tag in West face 35" Oak
- 145° 60.09' Set PK/lapeer County tag in Southwest face clump 12" aspens
- 255° 33.00' Chiled "X" on South end 12" CMP culvert
- 290° 160.22' Set PK/Lapeer County tag in South face Utility pole



Signed by *Shelby W. Money* Date Nov. 3, 1995
Surveyor's Michigan License No. 30092