

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER Located in: IMLAY TOWNSHIP Corner Code #
(County)

1. Public Land Survey T 7N R 12E A-7
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

RECEIVED FOR RECORD

94 DEC -9 PM 3: 19

LIBER NO. 005 PAGE 145
Nelson DeWangh
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on SEPTEMBER 2, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1) G.L.O. 1824 PAGE 590	LUCIUS LYON	NO WITNESSES SET
2) LCRC 1991 LIBER 004 PAGE 380	EARL E. GRAVLIN, #23510	FOUND, 32 LINKS SOUTH M-7, T.7N., R.11E.
3) SURVEY 1980 LIBER 005 PAGE 841	HAROLD N. ERLICH, #18986	FOUND, 1/2" IRON
4) SURVEY 1989 LIBER 008 PAGE 460	EARL E. GRAVLIN, #23510	FOUND, IRON BAR
5) SURVEY 1993 LIBER 010 PAGE 248	EARL E. GRAVLIN, #23510	FOUND, 1/2" IRON
		FOUND, 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND, 1/2" REBAR IN GRAVEL ROAD NO OCCUPATION LINES TO EAST

WITNESSES FOUND REFERENCING ITEMS 2, 4, AND 5
N 30° W 91.81' FOUND, TELEPHONE POLE
N 45° E 37.75' FOUND, 6" ASPEN
S 45° E 36.61' FOUND, 6" CEDAR

WITNESSES FOUND REFERENCING ITEM 3
N 30° W 74.48' FOUND, POWER POLE
S 40° W 50.92' FOUND, FENCE POST
S 60° E 29.06' FOUND, 12" ASH

G.L.O. OFFSET IS 32 LINKS SOUTH 21.12' FOUND M-7, T.7N., R.11E. 21.20'
A-7 TO A-6 T.7N., R.12E. G.L.O. (POST FOR A-6 NEVER SET) CHAINS MEASURED 2652.14'
A-7 TO A-8 T.7N., R.11E. G.L.O. (POST FOR A-8 NEVER SET) CHAINS MEASURED 2639.60'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND, 1/2" REROD
SET, BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED #30092 / A-7 ON A 1/2" X 18" REBAR

AZIMUTH 90° 41.48'	SET,	NAIL W/LAPEER TAG IN THE SOUTHWEST FACE OF A 12" CEDAR
AZIMUTH 20° 59.60'	SET,	"X" ON EAST END OF AN 18" C.M.P., 65± NORTH OF BELLE RIVER ROAD
AZIMUTH 330° 68.00'	SET,	"X" ON WEST END OF AN 18" C.M.P., 65± NORTH OF BELLE RIVER ROAD
AZIMUTH 340° 91.78'	SET,	NAIL WITH LAPEER TAG IN THE NORTHEAST FACE OF A UTILITY POLE
AZIMUTH 00° 21.20'	FOUND,	M-7, T.7N., R.11E. / ATTICA TOWNSHIP

PEER GROUP
APPROVED LAND CORNER

Signed by *Shelby W. Money* PA 345 OF 1000 Date December 2, 1994
Surveyor's Michigan License No. 30092

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-9-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1979
REVISED JAN. 1983

LIBER 0005 PAGE 0145

