

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> (County)	Located In: IMLAY TOWNSHIP	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>12E</u>	<u>A-8</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED FOR RECORD

94 DEC -9 PM 3:18

LIBER NO. 65 PAGE NO. 144
Historic Deeds
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on SEPTEMBER 2, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1) A-8 G.L.O. POST NOT SET
- 2) A-8 NO LCRC OR SURVEY ON RECORD
- 3) M-8 G.L.O. 1822 PAGE 379 JOSEPH WAMPLER SET POST NO WITNESSES FOUND
- 4) M-8 WITNESS 1987 UNRECORDED LAPEER COUNTY ROAD COMMISSION FOUND, UNKNOWN
- 5) M-8 LCRC 1986 LIBER 004 PAGE 117 BERNARD HENDERSON, #16043 FOUND, 1/2" IRON
- 6) M-8 SURVEY 1987 LIBER 007 PAGE 486 BERNARD HENDERSON, #16043 FOUND, 1/2" IRON BAR
- 7) M-8 SURVEY 1987 LIBER 007 PAGE 592 BERNARD HENDERSON, #16043 FOUND, 1/2" IRON
- 8) M-8 SURVEY 1991 LIBER 009 PAGE 230 HAROLD N. ERLICH, #18986 FOUND, 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-8 FOUND, CORNER M-8, T.7N., R.11E. 1/2" REBAR IN GRAVEL ROAD / NORTH, SOUTH AND WEST
- A-8 FENCE LINE TO THE EAST / FENCE RIGHT-OF-WAY - STONE AND STUMPS 10'± WIDE
- M-8 WITNESSES FOUND REFERENCING ITEMS 4, 5, 6, 7, AND 8
 - N 75° E 21.45' FOUND, 18" CHERRY
 - EAST 40.35' FOUND, 3" MAPLE
 - S 30° W 56.25' FOUND, TELEPHONE POLE
 - S 50° W 51.07' FOUND, 20" CHERRY
- A-8 G.L.O. OFFSET CALCULATED WOULD BE 5'± NORTH
G.L.O. AT A-7, T.7N., R.12E. IS 32 LINKS SOUTH 21.12'
G.L.O. AT A-9, T.7N., R.12E. IS 47 LINKS NORTH 31.02'
- A-8 TO A-7 T.7N., R.12E. G.L.O. (POST FOR A-8 NEVER SET) CHAINS MEASURED 2639.60'
- A-8 TO A-9 T.7N., R.12E. G.L.O. (POST FOR A-8 NEVER SET) CHAINS MEASURED 2634.10'
- A-8 COMMON CORNER TO M-8, T.7N., R.11E. / ATTICA TOWNSHIP



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET, BRASS LAPEER COUNTY REMONUMENTATION CAP STAMPED #30092 / M-8 ON A 1/2" X 18" REBAR
- AZIMUTH 70° 21.44' SET, NAIL W/LAPEER TAG IN THE NORTH FACE OF AN 18" CHERRY
- AZIMUTH 90° 40.40' SET, NAIL W/LAPEER TAG IN THE NORTH FACE OF AN 8" OAK
- AZIMUTH 210° 56.18' SET, NAIL W/LAPEER TAG IN THE WEST FACE OF A UTILITY POLE
- AZIMUTH 250° 50.87' SET, NAIL W/LAPEER TAG IN THE NORTH FACE OF AN 18" CHERRY

Signed by *Shelby W. Money* Date December 2, 1994
Surveyor's Michigan License No. 30092

CHERRY GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY