

MAR 29 1999

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 JAN -6 PM 1:21

For corners in

LAPEER  
(County)

Located In:  
IMLAY TWP

Corner Code #

- 1. Public Land Survey      T 7N R 12E      A-10
- T      R
- T      R
- T      R
- 2. Property Controlling    S      T      R
- in Section                    S      T      R
- 3. Miscellaneous            S      T      R
- Property in Sec.           S      T      R

437

Melissa DeVaugh  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Shelby W Money, in a field survey on October 8

, 19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Township line surveyed in 1816 by Wampler for T7N, R11E Attica Twp. No 1/2 mile post for section 30 of Imlay Twp being set. T7N, R12E was subdivided in 1816.

1. L2, Pg 343, July 1973 by Herbert Kobs, Found 5/8" dia. bar in gravel road.

APPROVED LAND CORNER  
LAPEER COUNTY  
RAY DAVIS P.S. CO. SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set a 1/2" iron in the centerline of Summers Road 61.50' north of M-10, T7N, R11E 0.92' east of line with M-10 and M-9 of T7N, R11E as indicated on the MDOT right of way maps for I-69.

1. P. K. nail & washer in 30" maple N.E. 116.84. 116.43' Measure.

D. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


A-10 Set a 1/2" iron with a 2" diameter brass cap stamped LAPEER COUNTY REMONUMENTATION, PS#30092.

- 1. Az 15° 116.43' to P. K. nail W/Lapeer Remon Tag set in west face of a 36" maple.
- 2. Az 115° 208.72' to P. K. nail W/Lapeer Remon Tag set in north face of a utility pole.
- 3. Az 180° 200.26' to P. K. nail W/Lapeer Remon Tag set in concrete joint of eastern slope pavement of west bound I-69 bridge.
- 4. Az 190° 201.07' to P. K. nail W/Lapeer Remon Tag set in concrete joint of western slope pavement of west bound I-69 bridge
- 5. Az 250° 134.73' to Nail W/Lapeer Witness Tag found in north face of a 28" maple.

FIELD MEASUREMENTS    A-10 TO M-10 (T7N, R11E) 61.50'      A-10 TO A-11 2653.61'  
   A-10 TO M-9 (T7N, R11E) 2615.77

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Shelby W Money Date 12/30/98  
Surveyor's Michigan License No. 30092



A