

MAR 29 1999

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER
(County)

Located In:
IMLAY TWP

Corner Code #

- 1. Public Land Survey T 7N R 12E A-11
- T R
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

RECEIVED FOR RECORD

99 JAN -6 PM 1:22

Melissa D. Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

438

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Shelby W Money, in a field survey on October 8, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Township line surveyed in 1816 by Wampler for T7N, R11E Attica Twp. No corner post for section 30 of Imlay Twp being set. T7N, R12E was subdivided in 18, a post was set common to sections 30 and 31, 83 lks north of corner post for Attica Twp.

- 1. L2, Pg 345, July 1973 LCRC by Herbert Kobs, Found 1/2" dia. form pin with large head in gravel road.
- 2. L4, Pg 08, August 1980 LCRC by Joseph Macay, Found 1/2" iron rod.
- 3. L7, Pg 147 October 1985 survey by Earl Gravlin, Found 1/2" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: DATE 10-13-98

Found iron is 1 ft west of the physical centerline of Summers Road, which has a gravel surface and runs north and south. Corner is 19' north of the centerline of Hunters Creek Road to the east which is deflecting south to meet Hunters Creek Road to the west. The following witnesses from the LCRC were used to locate the corner:

- 1. South 65.95' to Railroad spike (S. E. Cor. Sec. 25 Attica) L2, Pg 345

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Replaced the form pin with a 1/2" iron with a 2" diameter brass cap stamped LAPEER COUNTY REMONUMENTATION, PS#30092.

- 1. Az 50° 84.02' to spike found in southeast face of a utility pole.
- 2. Az 170° 106.12' to Nail W/Lapeer Witness Tag found in north face of 8" diameter pole with telephone box.
- 3. Az 185° 145.41' to P. K. nail W/Lapeer Remon Tag set in west face of a multi 6" crab apple.
- 4. Az 215° 122.57' to Nail W/Lapeer Witness Tag found in northwest face of a utility pole.
- 5. Az 320° 87.12' to Nail W/Lapeer Witness Tag found in southwest face of a utility pole.

FIELD MEASUREMENTS A-11 TO M-11 (T7N, R11E) 66.05 GLO 54.78'
A-11 TO M-10 (T7N, R11E) 2592.12'
A-11 TO A-10 2653.61'

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Shelby W. Money Date 12/20/98
Surveyor's Michigan License No. 30092

