

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

LAPEER
(County)

Located In:
IMLAY TWP

Corner Code #

- 1. Public Land Survey T 7N R 12E Corner Code # A-12
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

RECEIVED FOR RECORD

99 JAN -6 PM 1:22

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

439

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Shelby W Money, in a field survey on October 8,
19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Township line surveyed in 1816 by Wampler for T7N, R11E Attica Twp. No quarter post for section 30 of Imlay Twp being set.

1. L2, Pg 673, September 1974 by Bernard Henderson, Found iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron is 2 ft east of the physical centerline of Summers Road, which has a gravel surface and runs north and south. A tree line extending to the east begins approximately 150 ft east of the corner. The corner is 2.36' east of township line(T7N, R11E) M-12 to M-11. The following witnesses from the LCRC were used to locate the corner:

1. S 60° W 42.25' Power Pole. Measured 41.89' to a nail W/Lapeer Witness Tag. This nail was placed as a witness for corner M-13 of T7N, R11E, Attica Twp. No recorded certificate was found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 Placed a 2" diameter brass cap stamped LAPEER COUNTY REMONUMENTATION, PS#30092 on found 1/2" iron

- 1. Az 15° 124.21' to P. K. & Lapeer County Remon Tag set in west face of a 10" elm.
- 2. Az 115° 75.42' to P. K. & Lapeer County Remon Tag set in north face of a utility pole.
- 3. Az 235° 41.41.89' to Nail W/Lapeer Witness Tag found in southeast face of a utility pole.
- 4. Az 290° 25.05' to a chisel "x" in top of concrete abutment.

FIELD MEASUREMENTS A-12 TO M-12 (T7N, R11E) 32.60'
A-12 TO M-11 (T7N, R11E) 2631.64'
A-12 TO A-13 2696.46'

REGISTER GROUP
REGISTERED CORNER
LAPEER COUNTY
MICHIGAN
DATE 10-13-98

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Shelby W Money
Surveyor's Michigan License No. 30092

Date 10/13/98

