

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
99 JAN -6 PM 1:22

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

440

Register of Deeds Stamp & File Number

For corners in

LAPEER
(County)

Located In:
IMLAY TWP

Corner Code #

- 1. Public Land Survey T 7N R 12E A-13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Shelby W Money, in a field survey on October 8

19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Township line surveyed in 1822 by Wampler for T7N, R11E Attica Twp, commencing on the East line of section 36 for T7N, R11E.

- 1. L2, Pg 701, November 1974 LCRC by Stephen Swarts, Found 1/2" rod in concrete.
- 2. L3, Pg 449, June 1978 LCRC by Bernard Henderson, Found 1/2" rod in concrete.
- 3. L3, Pg 338, June 1975 survey by Kay Engineering, Found concrete monument.
- 4. L4, Pg 177, July 1977 survey by Kay Engineering, Found concrete monument.
- 5. L4, Pg 716, June 1978 survey by Henderson Bates, Found 1/2" rod in concrete.
- 6. L5, Pg 749, June 1978 survey by Henderson Bates, Found 1/2" rod in concrete.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PEER GROUP
APPROVED LAND CORNER
MICHIGAN P.A. 94 OF 1990
LAPEER COUNTY

DATE 10-13-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2 iron in concrete with Lapeer County Remonumentation Brass Cap Marked 30092 / M-13. Corner previously remonumented as M-13 of Attica Twp. (T7N, R11E). The following witnesses listed below are from the LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 Found a 1/2 iron in concrete with Lapeer County Remonumentation Brass Cap Marked 30092 / M-13.

- 1. Az 20° 70.32' to Nail W/Lapeer Witness Tag found in west face of a 12" Elm.
- 2. Az 80° 26.50' to Nail W/Lapeer Witness Tag found in north face of a 15" Locust.
- 3. Az 190° 101.12' to Nail W/Lapeer Witness Tag found in east face of 24" Elm.
- 4. Az 205° 5.00' Nail W/Lapeer Witness Tag found in northwest face of a 21" Locust.
- 5. East 8.0' to west face of a fence post.

FIELD MEASUREMENTS A-13 TO A-12 2696.46 A-13 TO M-1 Dryden 710.57

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 30092

Date 12/30/98

