

REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lapeer</u> (County)	Located In: Imlay Township	Corner Code # H-13
1. Public Land Survey	T 7 N R 12 E	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD

94 DEC 29 AM 10:24

LIBER NO. 25 PAGE NO. 198

REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Shelby W. Money, in a field survey on 11-18, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Joseph Wampler, D.S. 1822 pages 556-560 Set post No witnesses found
2. Gilbert Bates 1865 pages 348-349 Stone 23" -13" - 3"
3. LCRC recorded by Earl Gravlin, P.S. # 23510 on 11-22-77 in liber 3, page 402, of corners, as a found large rock with a chisled "X" on top.
4. Recorded survey by Earl Gravlin, P.S. # 23510 on 11-22-77 in liber 5, page 580, of surveys, as a found large rock with a chisled "X" on top.
5. LCRC recorded by Earl Gravlin, P.S. # 23510 on 2-6-80 in Liber 4, page 55 of corners as a found large rock with a chisled "X" on top.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a large rock (48" -30" -18") with a chisled "X" on top in remains of old fence line running East and West. No occupation to the North.

Found witnesses from items 3, 4 and 5 above:

- S 20° W 36.23' Nail in 6" Elm.
- S 60° E 5.91' Nail in 8" Elm.
- N 80° W 4.32' Nail in 4" Elm.


Distances: East to I-13 Imlay Township 2614.33 (Gilbert Bates 2629.44)
West to H-1 Almont Township 573.57'.
West to G-13 Imlay Township 2640.08" (Gilbert Bates 2629.44)'.
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard Lapeer County Remonumentation cap stamped "I-13 30092" on Iron drilled into rock at chisled "X".

Witnesses:

- Az 0° 3.5' 4' woven wire fence running East and West
- Az 10° 44.02' Set PK with Lapeer County tag in West face of 4" Maple
- Az 135° 52.10' North end 18" csp @ field drive
- Az 300° 3.02' Set PK with Lapeer County tag in Northeast face 14" stump

Signed by Shelby W. Money
Surveyor's Michigan License No. 30092



PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-28-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983