

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lapeer</u> (County)	Located In: Imlay Township	Corner Code # J-13
1. Public Land Survey	T <u>7N</u> R <u>12E</u>	<u>J-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED FOR RECORD

94 DEC 29 AM 10: 29

LIBER NO. 05 PAGE NO. 202

REGISTERED OFFICE
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Shelby W. Money, in a field survey on 11-13, '994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Joseph Wampler, D.S. Pages 556-560 Set Post No Witnesses found
Nothing else found for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fence lines to West, East and North. Tree row to North. Section corner is in the Belle River crossing from Northwest to Southeast.
Placed witness monument 70.0 feet north of corner on line of occupation

Distances: West to I-13, T7N, R12E Imlay Township 2620.08'
East to K-13, T7N, R12E Imlay Township 2620.08'
West to J-1, T6N, R12E Almont Township 344.85'


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a standard Lapeer County Remonumentation cap stamped "J-13 30092" on 1/2" rebar 18" long 70.0 feet north of corner..

Witnesses: Az 0° 35.56 Set PK with Lapeer County tag in East face 36" Oak
Az 95° 24.49 Set PK with Lapeer County tag in South face 4" Ash
Az 105° 75.77 Set PK with Lapeer County tag in South face 10" Poplar
Az 350° 44.55 Set PK with Lapeer County tag in West face 8" Elm

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-29-94



Signed by Shelby W. Money Date 12/29/94
Surveyor's Michigan License No. 30092