

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| _____ Lapeer _____ (County) | Located in: Imlay Township | Corner Code # |
|------------------------------------|-------------------------------|---------------|
| 1. Public Land Survey | T <u>7</u> N R <u>12</u> E | <u>K-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD

54 DEC 29 AM 10: 27

LIBER NO. 05 FILE NO. 200

Shelby W. Money

REGISTERED SURVEYOR
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Shelby W. Money, in a field survey on 11-13, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|---|---|----|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | | | | 3 | | | | | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 9 | | 9 | | 10 | | 11 | | | | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | | | 13 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | | | 24 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | | | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | | | 36 |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- Joseph Wampler, D.S. Pages 556-560 Set Post No Witnesses found
- Gilbert Bates 1865 Stake
- Recorded Survey by James Bailey, P.S. # 33968 in Liber 9, page 788, surveys as a found 1/2" Iron 9' south of the centerline of Burt Road.
- Recorded Survey by Earl Gravlin, P.S. 23510 on 8-3-93 in Liber 10, page 259, surveys as an unknown.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" iron 9' south of the centerline of Burt Road (gravel) along with the following witnesses from items 3 and 4 above.
Graham Road centerline to the North lines up with this Iron
N 35° E 55.31' Center telephone pedestal
South 21.78' Nail with tag fence post
S 10° W 22.69' PK in fence post.
S 65° W 47.83' Nail and tag in fence post.

Distances: West to J-13, T7N, R12E Imlay Township 2620.08'
West to K-1, T6N, R12E Almont Township 230.34'

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY
Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 12-28-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed as standard Lapeer County Remonumentation cap stamped "K-13 30092" on found Iron.

Witnesses: Az 30° 63.54' Set nail and Lapeer County tag in West face utility pole.
Az 40° 55.31' Center GTE telephone pedestal.
Az 135° 38.40' Set 1/2" rebar with traverse cap # 30092.
Az 180° 21.78' Found nail with MDSH tag in East face fence post.
Az 200° 22.78' Found Pk, set nail with Lapeer County tag East face fence post.
Az 330° 49.18' Set 1/2" rebar with Traverse cap # 30092

Signed by Shelby W. Money Date 12/22/94
Surveyor's Michigan License No. 30092

