

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>LAPEER</u> <small>(County)</small>	Located In: <u>IMLAY TOWNSHIP</u>	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>12E</u> T _____ T _____ T _____	<u>M-4</u> _____ _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

95 DEC 28 PM 2:38
 LIBER NO. 005 PAGE NO. 325
Melissa DeLuca
 REGISTER OF DEEDS
 LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James T. Bailey, in a field survey on November 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. G.L.O. (1822) WAMPLER D.S. SET POST NO WITNESSES FOUND
2. SURVEY (1990) ELRICH P.S. L.8 P. 927 FOUND 1/2" IRON
3. SURVEY (1994) BAILEY P.S. L.10 P.810 FOUND 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 JAMES T. BAILEY P.S. FOUND A 1/2" IRON ROD 6" BELOW GRADE 4' WEST OF THE CENTERLINE OF CADE ROAD (GRAVEL) ON THE CENTERLINE OF PETZ ROAD (GRAVEL) TO THE WEST. REMAINING WITNESSES FROM ITEMS 2 AND 3 ABOVE MATCH.

DISTANCES M-3 2678.68


PEER GROUP
 APPROVED LAND CORNER
 PA 845 CF 190
 LAPEER COUNTY

Ray Davis
 RAY DAVIS P.S. CO. SURVEYOR
 DATE 7-13-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 SET STANDARD LAPEER COUNTY REMONUMENTATION CAP ON FOUND 1/2" IRON.

- S.50°E. 43.11 SET PK NAIL W/ REMON TAG IN POWER POLE
- S.30°W. 91.90 SET PK NAIL W/ REMON TAG IN 12" ASH
- N.45°W. 43.10 SET PK NAIL W/ REMON TAG IN 12" ASH
- S.65°W. 106.08 SET PK NAIL W/ REMON TAG IN POWER POLE



Signed by *JT Bailey*
 Surveyor's Michigan License No. 33968

Date DECEMBER 20, 1995