

**SURVEY & REMONUMENTATION**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
LAPEER County Located In: IMLAY TOWNSHIP Corner Code #  
1. Public Land Survey T 7N R 12E M5  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD

95 JAN -3 PH 3: 48

LIDER NO. 05 PAGE NO. 203

*Melissa De Vaughn*

REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, JAMES T. BAILEY in a field survey on OCTOBER 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1822) JOSEPH WAMPLER SET POST 17" MAPLE N.88½°W. 27 LKS  
9" TREE N. 49°W. 57 LKS

SURVEY (1979) CHARLES GETZ UNRECORDED FOUND ½" IRON N.45°E. 29.74 NAIL  
IN COR. POST; S.45°E. 39.27 ROAD SIGN; SOUTH 5.4 TO ½" IRON AT NETTNEY RD.  
N.W. COR. SEC. 18, T7N-R13E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 JAMES T. BAILEY P.S. FOUND ½" REBAR 3" BELOW GRADE IN THE CENTERLINE OF CADE ROAD. FOUND 3 WITNESSES THAT VERIFY LOCATION FROM PREVIOUS SURVEY.


ACCEPTED ½" REBAR AS BEST LOCATION OF ORIGINAL POSITION OF THE NORTHEAST CORNER, SECTION 13, T7N - R12E, IMLAY TOWNSHIP.

PEER GROUP  
APPROVED LAND CORNER

PA 245 OF 1990  
LAPEER COUNTY  
*Ray Davis*  
RAY DAVIS P.C. CO. SURVEYOR  
DATE 1-3-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 ½" REROD W/ STANDARD REMONUMENTAION CAP



SOUTH 5/40 FD. CAPPED IRON NOT LEDGEABLE @ NETTNEY RL  
N.50°E. 30.14 SET NAIL W/ REMON TAG IN N.W. FACE COR.  
POST  
N.89°W. 73.04 SET NAIL W/ REMON TAG IN S. FACE 14" ASH  
S.50°W. 32.68 SET NAIL W/ REMON TAG IN N.W. FACE COR  
POST  
N.50°E. 30.19 FD. P.K. IN N.W. FACE COR. POST  
N.89°W. 73.12 FD. P.K. IN SOUTH FACE 14" ASH  
S.50°W. 32.71 FD. P.K. IN N.W. FACE COR. POST

Signed by *James Bailey* Date December 29, 1994

Surveyor's Michigan License No. 33968

LIBER 0005 PAGE 0203