

**SURVEY & REMONUMENTATION**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 JAN 19 PM 2: 27

LIBER NO. 05 PAGE NO. 216  
*Melissa De Vaughn*

REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

For corners in

Lapeer County

Located in: Imlay Township

Corner Code M7

- |                                      |                          |           |
|--------------------------------------|--------------------------|-----------|
| 1. Public Land Survey                | T <u>7N</u> R <u>12E</u> | <u>M7</u> |
|                                      | T _____ R _____          | _____     |
|                                      | T _____ R _____          | _____     |
|                                      | T _____ R _____          | _____     |
| 2. Property Controlling in Section   | S _____ T _____ R _____  | _____     |
|                                      | S _____ T _____ R _____  | _____     |
| 3. Miscellaneous Property in Sec.    | S _____ T _____ R _____  | _____     |
|                                      | S _____ T _____ R _____  | _____     |
| 4. Lot No. _____ Recorded Plat _____ |                          |           |
| 5. Private Claims _____              |                          |           |

Register of Deeds Stamp & File Number

I, James T. Bailey, in a field survey on December 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	13	12	11	10	9	8	7	6	5	4	3	2	1
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	25	24	23	22	21	20	19	18	17	16	15	14	13
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. (1822) Joseph Wampler SET POST 17" MAPLE N.88½°W. 27 LKS., 9" TREE N.49°W. 57 LKS.
- G.L.O. (1824) L. Lyon SET POST FOR N.W. CORNER, T7N-R12E, 52 LKS SOUTH OF M7, T7N-R12E SURVEY (1/2/91) Milletics P.S. UNRECORDED, FD. P.K. NAIL 23.2 N OF MON. BOX
- SURVEY (9/4/91) James T. Bailey P.S. UNRECORDED, FD. P.K. NAIL 23.2 N OF MON BOX
- SURVEY (1993) Russell L. Brown P.S. UNRECORDED, FD. HEX BAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 JAMES T. BAILEY P.S. FOUND P.K. NAIL 23.2' NORTH OF MON BOX 4" BELOW GRADE. 23.2' NORTH OF INTERSECTION IMLAY CITY ROAD AND CADE ROAD. 1.92' NORTH OF HEX BAR FROM ABOVE SURVEY BY BROWN P.S.

ACCEPTED P.K. NAIL AS BEST (OLDEST) LOCATION OF ORIGINAL POSITION OF THE NORTHEAST CORNER, SECTION 24, T7N-R12E, IMLAY TOWNSHIP.


PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 1-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 PLACED ½" ROD AND STANDARD REMONUMENTATION CAP IN MON. BOX.

- N.09°E. 161.26 SET NAIL W/ REMON TAG IN EAST FACE P.P.
- S.22°E. 83.99 SET NAIL W/ REMON TAG IN S.W. FACE P.P.
- S.17°W. 108.46 SET NAIL W/ REMON TAG IN GUY POLE
- N.28°W. 146.77 SET NAIL W/ REMON TAG IN N.W. FACE 8" ASH



Signed by *J. Bailey* Date DECEMBER 29, 1994  
Surveyor's Michigan License No. 32968