

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lapeer County Located in: IMLAY TOWNSHIP Corner Code ##

1. Public Land Survey	T <u>7N</u> R <u>12E</u>	<u>M8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

95 JAN -3 PM 3:58

LIBER NO. 05 PAGE NO. 212

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	20	20	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JAMES T. BAILEY in a field survey on OCTOBER 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. (1822) JOSEPH WAMPLER SET POST 14" BEECH S.41°W. 24 LKS, 17" TREE
N.34°W. 35 LKS
SURVEY (1993) RUSSEL L. BROWN UNRECORDED FD. ½" IRON, 3 WITS GIVEN
SURVEY (1994) JAMES T. BAILEY UNRECORDED FD. IRON, 4 WITS GIVEN

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 JAMES T. BAILEY P.S. FOUND ½" ROD 2' EAST OF CENTERLINE OF CADE ROAD 3"
BELOW GRADE ON THE EXTENSION OF A FENCE LINE TO THE WEST. FOUND 2 WITNESSES
FROM PREVIOUS SURVEYS THAT VERIFY LOCATION OF IRON FOUND. 1-3-95

M-8 to L-8 BAILEY MEAS. 2635.84, BROWN MEAS. 2636.00
M-8 to M-9 2645.08
M-8 to M-7 2645.08

ACCEPTED ½" ROD AS BEST LOCATION OF ORIGINAL POSITION OF THE EAST ¼ CORNER, SECTION 24, T7N-R12E, IMLAY TOWNSHIP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 SET STANDARD REMONUMENTATION CAP ON FOUND ½" ROD.

S.05°W. 29.88 SET NAIL W/ REMON TAG IN S. FACE GUY POLE
N.45°W. 67.22 SET NAIL W/ REMON TAG IN N.E. FACE POWER POLE
N.40°E. 59.28 SET NAIL W/ REMON TAG IN N.W. FACE POWER POLE
S.25°E. 73.65 SET NAIL W/ REMON TAG IN N.E. FACE POWER POLE
WEST 33.00 FND. ½" IRON
S.25°E. 73.54 FND. P.K. N.E. FACE POWER POLE



Signed by JT Bailey Date DECEMBER 29, 1994
Surveyor's Michigan License No. 33968